



BOBBY JINDAL
GOVERNOR

STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
P.O. Box 94245
Baton Rouge, Louisiana 70804-9245
www.dotd.la.gov
225-379-1485



WILLIAM D. ANKNER, Ph.D.
SECRETARY

September 18, 2009

STATE PROJECT NO. 240-03-0027
FEDERAL AID PROJECT NO. 3091(007)
WEEKS ISLAND BRIDGES
ROUTE LA 83
IBERIA PARISH

SUBJECT: ADDENDUM NO. 3 (CONSTRUCTION PROPOSAL REVISION)
ELECTRONIC BIDDING AMENDMENT NO. 1

Gentlemen:

The following proposal revisions dated 09/18/09 on the captioned project for which bids will be received on Wednesday, September 30, 2009 have been posted on <http://www.dotd.la.gov/cgi-bin/construction.asp>.

1. Revised the Schedule of Items as follows: (9 pages)
 - a. Revised Quantities for Items 202-02-38500, 303-01-00400, 805-01-00600 and 806-01-00100.
 - b. Deleted Items 203-03-00100 and 304-05-00100.
 - c. Added Items 203-04-00100, 203-07-00200 and 302-02-06000.

Please note these revisions in the proposal and bid accordingly. Mandatory electronic bidding is required for this project, and electronic bids and electronic bid bonds must be submitted via www.bidx.com for this letting date.

Sincerely,

RANDAL D. SANDERS, P. E.
CONTRACTS & SPECIFICATIONS ENGINEER

Attachments

cc: Mr. Brian Buckel
Mr. Bill Fontenot
Mr. Chris Lissard
Mr. Jenan Nekleh
Mr. Eric Burges
Mr. Masood Rasoulain



9/18/2009

Louisiana Department of Transportation and Development
Proposal Schedule of Items

Page: 1

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0001	201-01-00100	Clearing and Grubbing		LUMP SUM
				Dollars
				Cents
0002	202-01-00100	Removal of Structures and Obstructions		LUMP SUM
				Dollars
				Cents
0003	202-02-04000	Removal of Bridge (STA 210+00; 24' X 300' STEEL BRIDGE)	1.000	EACH
				Dollars
				Cents
0004	202-02-04000	Removal of Bridge (STA 146+31.72; 24' X 370' STEEL SWINGSPAN BRIDGE)	1.000	EACH
				Dollars
				Cents
0005	202-02-12300	Removal of Fender System	1.000	EACH
				Dollars
				Cents
0006	202-02-38500	Removal of Surfacing and Stabilized Base	10,071.760	SQYD
				Dollars
				Cents
0007	203-01-00100	General Excavation (Plan Quantity)	1,015.000	CUYD
				Dollars
				Cents
0009	203-08-00100	Geotextile Fabric	17,700.000	SQYD
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development
Proposal Schedule of Items

Page: 2

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0010	204-06-00100	Temporary Silt Fencing	13,600.000	LNFT
				Dollars
				Cents
0011	303-01-00400	In-Place Cement Stabilized Base Course (12" Thick)	2,291.700	SQYD
				Dollars
				Cents
0013	401-02-00100	Aggregate Surface Course (Adjusted Vehicular Measurement)	100.000	CUYD
				Dollars
				Cents
0014	402-01-00100	Traffic Maintenance Aggregate (Vehicular Measurement)	480.000	CUYD
				Dollars
				Cents
0015	502-01-00100	Superpave Asphaltic Concrete	2,986.200	TON
				Dollars
				Cents
0016	502-01-00200	Superpave Asphaltic Concrete, Drives, Turnouts and Miscellaneous	271.300	TON
				Dollars
				Cents
0017	509-01-00100	Cold Planing Asphaltic Pavement (4" Thick)	1,528.000	SQYD
				Dollars
				Cents
0018	701-05-01060	Side Drain Pipe (24" RCP/PP/CMP)	20.000	LNFT
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 3

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0019	704-03-00100	Blocked Out Guard Rail	1,425,000	LNFT
				Dollars
				Cents
0020	704-08-00200	Guard Rail Transitions (Double Thrie Beam)	200,000	LNFT
				Dollars
				Cents
0021	704-11-00200	Guard Rail End Treatment (Tangent)	8,000	EACH
				Dollars
				Cents
0022	708-01-00100	Right-of-Way Monument	20,000	EACH
				Dollars
				Cents
0023	708-02-00100	Right-of-Way Monument Witness Post	20,000	EACH
				Dollars
				Cents
0024	712-04-00100	Flexible Revetment	856,000	SQYD
				Dollars
				Cents
0025	713-01-00100	Temporary Signs and Barricades		LUMP SUM
				Dollars
				Cents
0026	713-04-01000	Temporary Pavement Markings (Solid Line) (4" Width)	1,979	MILE
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development
Proposal Schedule of Items

Page: 4

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0027	713-07-00100	Temporary Precast Concrete Barrier (Contractor Furnished)	114.000	EACH
				Dollars
				Cents
0028	722-02-00100	Project Site Laboratory (Equipped)	1.000	EACH
				Dollars
				Cents
0029	727-01-00100	Mobilization		LUMP SUM
				Dollars
				Cents
0030	729-16-00300	Object Marker Assembly (Type 3)	8.000	EACH
				Dollars
				Cents
0031	730-09-00100	Electrical System		LUMP SUM
				Dollars
				Cents
0032	731-01-00100	Nonreflectorized Raised Pavement Markers	161.000	EACH
				Dollars
				Cents
0033	731-02-00100	Reflectorized Raised Pavement Markers	150.000	EACH
				Dollars
				Cents
0034	732-02-02000	Plastic Pavement Striping (Solid Line) (4" Width) (Thermoplastic 90 mil)	2.267	MILE
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 5

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0035	732-03-02000	Plastic Pavement Striping (Broken Line) (4" Width) (Thermoplastic 90 mil)	1.134	MILE
				Dollars
				Cents
0036	739-01-00100	Hydro-Seeding	1.230	ACRE
				Dollars
				Cents
0037	740-01-00100	Construction Layout		LUMP SUM
				Dollars
				Cents
0038	804-01-00300	Precast Concrete Piles (16")	15,976.000	LNFT
				Dollars
				Cents
0039	804-01-00600	Precast Concrete Piles (24")	2,118.000	LNFT
				Dollars
				Cents
0040	804-01-00700	Precast Concrete Piles (30")	1,104.000	LNFT
				Dollars
				Cents
0041	804-02-00200	Treated Timber Piles (Coastal Treatment)	9,300.000	LNFT
				Dollars
				Cents
0042	804-05-00300	Precast Concrete Test Piles (16")	2.000	EACH
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 6

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0043	804-09-00100	Loading Test Piles	2.000	EACH
				Dollars
				Cents
0044	804-10-00100	Reloading Test Piles	2.000	EACH
				Dollars
				Cents
0045	804-11-00100	Redriving Test Piles	2.000	EACH
				Dollars
				Cents
0046	804-12-00100	Loading Permanent Piles	2.000	EACH
				Dollars
				Cents
0047	804-17-00100	Dynamic Monitoring	6.000	EACH
				Dollars
				Cents
0048	805-01-00600	Class A Concrete (Piers)	187.450	CUYD
				Dollars
				Cents
0049	805-01-00700	Class A Concrete (Bents)	449.350	CUYD
				Dollars
				Cents
0050	805-01-00900	Class A Concrete (Counterweights)	25.850	CUYD
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 7

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0051	805-02-00400	Class A(M) Concrete (Bents)	42.840	CUYD
				Dollars
				Cents
0052	805-03-00100	Class AA Concrete	1,981.880	CUYD
				Dollars
				Cents
0053	805-11-00100	Strip Seal Joints	65.660	LNFT
				Dollars
				Cents
0054	806-01-00100	Deformed Reinforcing Steel	490,998.000	LB
				Dollars
				Cents
0055	807-08-00100	Structural Metalwork INCLUDES 245400 LBS. OF GRADE 50 STEEL AND 316307 LBS. OF GRADE 36 STEEL		LUMP SUM
				Dollars
				Cents
0056	808-01-00100	Steel Grid Flooring	3,229.300	SQFT
				Dollars
				Cents
0057	809-01-00100	Movable Bridge Machinery		LUMP SUM
				Dollars
				Cents
0058	809-02-00100	Traffic Barriers		LUMP SUM
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 8

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0059	809-03-00100	Operating House		LUMP SUM
				Dollars
				Cents
0060	810-01-00100	Concrete Railing (Standard Barrier)	3,177.170	LNFT
				Dollars
				Cents
0061	810-02-00100	Steel Railing	366.680	LNFT
				Dollars
				Cents
0062	810-03-00100	Pipe Railing	246.840	LNFT
				Dollars
				Cents
0063	812-01-00200	Treated Timber (Coastal Treatment)	38.090	MFBM
				Dollars
				Cents
0064	813-01-00100	Concrete Approach Slabs	300.740	SQYD
				Dollars
				Cents
0065	813-02-00100	Concrete Approach Slabs (Pile Supported)	612.860	SQYD
				Dollars
				Cents
0066	NS-300-00060	Geogrid	17,700.000	SQYD
				Dollars
				Cents



9/18/2009

Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page: 9

Contract ID: 240-03-0027

Project(s): 240-03-0027

SECTION: 1

General Items

Proposal Line Number	Item ID	Description Unit Price (In Words, Ink or Typed)	Approximate Quantity	Unit of Measure
0067	NS-700-00180	Impact Attenuator (Construction Zone)	2.000	EACH
				Dollars
				Cents
0068	NS-800-00080	Dynamic Analysis	2.000	EACH
				Dollars
				Cents
0069	NS-813-00001	Settlement Plate Installation & Monitoring	9.000	EACH
				Dollars
				Cents
0070	203-04-00100	Nonplastic Embankment	16,186.000	CUYD
				Dollars
				Cents
0071	203-07-00200	Borrow (Vehicular Measurement) (Selected Soils)	200.000	CUYD
				Dollars
				Cents
0072	302-02-06000	Class II Base Course (12" Thick)	12,055.000	SQYD
				Dollars
				Cents

Section: 1

Total:

Items Total:

Cost Plus Time	Road User Cost Per Unit	Unit Type	Number of Units Bid
01	Calendar Days - A+B	3,000.00	Days

Total Bid: