# STATE OF LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT

### LETTER BID PROPOSAL



STATE PROJECT NO. 256-06-0012 LA 942 – ST. JAMES PARISH LINE ASCENSION PARISH ROUTE LA 44

#### STATE PROJECT NO. 256-06-0012 TABLE OF CONTENTS

THE OF CONTENTS	
	Page No.
Title Sheet	A-1
Table of Contents	B-1
Notice to Contractors	
Special Provisions	D-1 thru D-11
Supplemental Specifications:	
Supplemental Specifications for 2006 Standard Specifications (08/08)	E-1 thru E-33
Plans (14 sheets)	F-1 thru F-13
Construction Proposal Information or Returnables:	
Title Sheet	G-1
Bid Bond	H-1
Schedule of Items	I-1 thru I-4
Construction Proposal Signature and Execution Form.	J-1 thru J-2

#### NOTICE TO CONTRACTORS (11/08)

Sealed paper bids for the following project will be received by the Department of Transportation and Development (DOTD). Paper bids can be delivered to the DOTD District 61Headquarters Administration Building, 8100 Airline Highway, Room 4, Baton Rouge, Louisiana 70815 until 10:00 a.m on TUESDAY, APRIL 21, 2009. Beginning at 10:00 a.m., all bids will be publicly opened and presented. The contractor's license number must appear on the bid envelope. No bids will be received after 10:00 a.m. or if the contractor's license number is not printed on the outside of the bid envelope. Any person requiring special accommodations shall notify DOTD at (225) 231-4100 not less than 3 business days before bid opening.

#### **STATE PROJECT NO. 256-06-0012**

DESCRIPTION: LA 942 - ST. JAMES PARISH LINE

**ROUTE: LA 44** 

PARISH: ASCENSION LENGTH: 1.800 miles.

TYPE: PATCHING AND OVERLAY

LIMITS: State Project No. 256-06-0012: ON ROUTE LA 44 FROM LA 942 TO ST. JAMES

**PARISH LINE** 

ESTIMATED COST RANGE: \$250,000 - \$500,000

PROJECT ENGINEER: ELISAR, AARON; 43133-1 HIGHWAY 30, GONZALES, LA 70737;

(225) 675-5320

PROJECT MANAGER: TUREAU, JOEY; (225) 474-2022

COST OF PROPOSAL FORMS: FREE

COST OF PLANS: FREE

Bids must be prepared and submitted in accordance with Section 102 of the 2006 Louisiana Standard Specifications for Roads and Bridges as amended by the project specifications, and must include all information required by the proposal.

#### NOTICE TO CONTRACTORS (CONTINUED)

Plans and specifications may be seen at the Project Engineer's office. Upon request, the Project Engineer will show the work.

The U. S. Department of Transportation (DOT) operates a toll free "Hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., eastern time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should call 1-800-424-9071. All information will be treated confidentially and caller anonymity will be respected.

GENERAL BIDDING REQUIREMENTS (08/06): The specifications, contract and bonds governing the construction of the work are the 2006 Edition of the Louisiana Standard Specifications for Roads and Bridges, together with any supplementary specifications and special provisions attached to this proposal.

Bids shall be prepared and submitted in accordance with Section 102 of the Standard Specifications.

The plans herein referred to are the plans approved and marked with the project number, route and Parish, together with all standard or special designs that may be included in such plans. The bidder declares that the only parties interested in this proposal as principals are those named herein; that this proposal is made without collusion or combination of any kind with any other person, firm, association, or corporation, or any member or officer thereof; that careful examination has been made of the site of the proposed work, the plans, Standard Specifications, supplementary specifications and special provisions above mentioned, and the form of contract and payment, performance, and retainage bond; that the bidder agrees, if this proposal is accepted, to provide all necessary machinery, tools, apparatus and other means of construction and will do all work and furnish all material specified in the contract, in the manner and time therein prescribed and in accordance with the requirements therein set forth; and agrees to accept as full compensation therefore, the amount of the summation of the products of the quantities of work and material incorporated in the completed project, as determined by the engineer, multiplied by the respective unit prices herein bid.

It is understood by the bidder that the quantities given in this proposal are a fair approximation of the amount of work to be done and that the sum of the products of the approximate quantities multiplied by the respective unit prices bid shall constitute gross sum bid, which sum shall be used in comparison of bids and awarding of the contract.

The bidder further agrees to perform all extra and force account work that may be required on the basis provided in the specifications.

The bidder further agrees that within 15 calendar days after the contract has been transmitted to him, he will execute the contract and furnish the Department satisfactory surety bonds.

If this proposal is accepted and the bidder fails to execute the contract and furnish bonds as above provided, the proposal guaranty shall become the property of the Department; otherwise, said proposal guaranty will be returned to the bidder; all in accordance with Subsection 103.04.

MAINTENANCE OF TRAFFIC (08/06): Subsection 104.03 of the 2006 Standard Specifications is amended to include the following requirements.

The contractor shall provide for and maintain through and local traffic at all times and shall conduct his operations in such manner as to cause the least possible interference with traffic at junctions with roads, streets and driveways.

Between October 1 and January 31, the contractor shall maintain the highway in a condition suitable for large scale sugar cane hauling operations and prior thereto shall perform only those items which will not interfere with the condition of the highway for heavy hauling operations. During this period, the contractor shall provide all equipment and material necessary to keep the highway in satisfactory condition. If the contractor does not properly maintain the highway, the Department reserves the right to maintain same with its own equipment, labor and material and deduct costs of such maintenance from payments for the work. If it becomes necessary to suspend construction operations for heavy hauling during the sugar cane season,

contract time will not be assessed for said period of suspension; however, maintenance of traffic shall be continued by the contractor during such period of suspension.

The contractor shall conduct his paving operations on one side of the roadway at a time. The side of the roadway, including shoulder, that is open to traffic shall be clear at all times.

When the plans show asphaltic concrete pavement layers to be placed in thicknesses of 2 inches (50 mm) or less, the contractor will be permitted to pave in one lane for a full day; the adjacent lane may be paved the following workday. When pavement layers are greater than 2 inches (50 mm) thickness, the contractor shall place approximately 1/2 of each day's production in one lane and the remainder in the adjacent lane.

At the end of each day's paving operations, temporary pavement markings shall be in place and proper signs and barricades displayed. During the period that all lanes are open to traffic, the contractor shall neither store material nor park equipment on roadway shoulders.

When asphaltic concrete pavement is cold planed to a depth of 2 inches (50 mm) or less, the contractor will be permitted to cold plane in one lane for a full day; the adjacent lane may be cold planed the following workday. When the depth of cold planing is greater than 2 inches (50 mm), the contractor shall cold plane approximately 1/2 of each day's production in one lane and the remainder in the adjacent lane.

Any work concerning all items of this project can only be performed and completed when the stage of the Mississippi River is below elevation +11.0 feet National Geodetic Vertical Datum (NGVD) on the Carrollton gage at New Orleans, Louisiana. Information concerning the current river stages may be obtained at <a href="www.rivergages.com">www.rivergages.com</a> or by calling (504)862-2461. During this period, the contractor shall provide all equipment and material necessary to keep the highway in satisfactory condition. If the contractor does not properly maintain the highway, the Department reserves the right to maintain same with its own equipment, labor and material and deduct costs of such maintenance from payments for the work. If it becomes necessary to suspend construction operations during the high water season, contract time will not be assessed for said period of suspension; however, maintenance of traffic shall be continued by the contractor during such period of suspension.

**SUBLETTING OF CONTRACT (01/83):** In accordance with Subsection 108.01 of the Standard Specifications, the following items are designated as "Specialty Items":

Item 729-16-B, Object Marker Assembly (Type 2)

Item 729-16-C, Object Marker Assembly (Type 3)

Item 731-02, Reflectorized Raised Pavement Markers

Item 732-02-A, Plastic Pavement Striping (Solid Line) (4" Width)

Item 732-03-A, Plastic Pavement Striping (Broken Line) (4" Width)

**PROSECUTION OF WORK (12/08):** Subsection 108.04, Prosecution of Work of the Standard Specifications as amended by the supplemental specifications thereto, is further amended as follows.

#### 108.04 PROSECUTION OF WORK.

Subpart (a), General is deleted and the following substituted.

(a) General: The contractor shall provide sufficient materials, equipment and labor to complete the project in accordance with the plans and specifications within the contract time. If the completed work is behind the approved progress schedule, the contractor shall take

immediate steps to restore satisfactory progress and shall not transfer equipment or forces from uncompleted work without prior notice to, and approval of, the engineer. Each item of work

shall be prosecuted to completion without delay. If prosecution of the work is discontinued for an extended period of time, the contractor shall give the engineer written notice at least 24 hours before resuming operations. The contractor's progress will be determined monthly at the time of each partial estimate, and will be based on the total amount earned by the contractor as reflected by the partial estimate. If the contractor's progress is behind more than 20 percent behind the elapsed contract time, the contractor may be notified that he is not prosecuting the work in an acceptable manner. If requested by the Department the contractor must meet with and provide the project engineer with an acceptable written plan which details how the contractor will re-gain lost progress and prosecute remaining work. If the contractor's progress is more than 30 percent behind the elapsed contract time, the contractor and the surety will be notified that he is not prosecuting the work in an acceptable manner. The contractor must meet with and provide the project engineer with an acceptable written plan which details how the contractor will re-gain lost progress and prosecute remaining work.

Subpart (b), Disqualification is deleted and the following substituted.

(b) Disqualification: A contractor who is in default in accordance with Subsection 108.09(a)(1) of and progress is deficient by 10 percent or more shall be immediately disqualified. The contractor shall remain disqualified until the project has received a final inspection and has been recommended for final acceptance. Should the surety or the Department take over prosecution of the work, the contractor shall remain disqualified for a period of one year from the completion of the project, unless debarment proceedings are instituted.

During the period of disqualification, the contractor will not be permitted to bid on contracts nor be approved as a subcontractor on contracts. Any bid submitted by the contractor during the period of disqualification will not be considered and will be returned.

**PAYMENT ADJUSTMENT (12/08):** Section 109, Measurement and Payment of the 2006 Standard Specifications and the supplemental specifications thereto, is amended to add the following.

This project is designated for payment adjustment for asphalt cements and fuels in accordance with Subsection 109.09 as follows.

#### 109.09 PAYMENT ADJUSTMENT (ASPHALT CEMENTS AND FUELS).

(a) General: Payment for contract items indicated herein will be adjusted to compensate for cost differentials of Performance Graded (PG) asphalt cements, gasoline, and diesel fuel when such costs increase or decrease more than 5 percent from the Department's established base prices for these items. The base price indices for asphalt cements and fuels will be the monthly price indices in effect at the time bids are opened for the project. The base price indices for asphalt cements will be as stated in paragraph (b) below. The base price index for fuels will be as stated in paragraph (c) below.

Payment adjustments will be made each monthly estimate period when a price index for this period varies more than 5 percent from its respective base price index. The monthly price indices to be used with each monthly estimate will be the price indices for the month in which the estimate period begins.

If the project is placed in default, payment adjustments will be based on the monthly price indices used for the last monthly estimate period prior to the project being placed in default, unless a monthly price index decreases in which case the lower monthly price index will be used.

If it is determined after completion of work on any eligible item that the total quantity paid to date must be adjusted to reflect more accurate quantity determinations, the Department will prorate the additional quantity to be added or subtracted over all previous estimate periods in

which the item of work was performed in order to determine additional payment adjustments. If payment adjustments were made during any of these partial estimate periods, this added or subtracted quantity that has been prorated will likewise have payment adjustments calculated and included.

(b) Performance Graded (PG) Asphalt Cements: The base price index will be the monthly price index in effect at the time of bid opening as shown elsewhere herein. The monthly price indices will be the average, excluding the extreme outliers, of the unit prices for PG 64-22, the average, excluding the extreme outliers, of the unit prices for PG 70-22m, and the average, excluding the extreme outliers, of the unit prices for PG 76-22m. The monthly prices for each of these asphalt materials will be F.O.B. refinery or terminal as determined from the quoted prices effective on the first calendar day of each month from suppliers of these materials. Suppliers considered are those who have requested to participate in the liquid asphalt index determination and have supplied materials on DOTD projects within the past twelve months. These suppliers and materials shall be listed on the Department's Qualified Products List (QPL 41) and must be marketed in Louisiana. For Asphalt Cements not listed above, the following shall be considered equivalent for payment adjustments:

Pay Item Equivalents Eligible for Asphalt Pay Adjustment

Performance Graded Asphalt Cement	Equivalent PG Asphalt Cement for Payment Adjustment
PG 58-28	PG 64-22
PG 64-22	PG 64-22
PG 70-22m	PG 70-22m
PG 76-22m	PG 76-22m
PG 82-22rm	PG 64-22

Payment adjustments will be made in accordance with the following formulas:

If Monthly Price Index exceeds Base Price Index,  

$$P_a = (A - 1.05B) \times C \times D \times (1.00 + T)$$

If Base Price Index exceeds Monthly Price Index,  

$$P_a = (0.95B - A) \times C \times D \times (1.00 + T)$$

Wh	eı	re.
VV II	С	ıc.

P<sub>a</sub> = Price adjustment (increase or decrease) for asphalt cement.

A = Monthly Price Index for respective PG 64-22, PG 70-22m, or PG 76-22m

in dollars per ton/megagram.

B = Base Price Index for respective PG 64-22, PG 70-22m, or PG 76-22m in

dollars per ton/megagram.

C = Tons/megagrams of asphaltic concrete.

D = Percent of respective asphalt cement, per job mix formula, in decimals.

T = Louisiana sales tax percentage, in decimals.

(Note: Local tax is not considered)

The engineer will furnish the weights (mass) of asphaltic concrete placed during the monthly estimate period with the respective asphalt cement content, excluding the asphalt content in reclaimed asphaltic pavement (RAP) as per job mix formula. If the asphalt cement

content changes during the estimate period, the respective weight (mass) of asphaltic concrete produced at each cement content will be reported.

All contract pay items using PG 58-28, PG 64-22, PG 70-22m, PG 76-22m, and PG 82-22rm shall be eligible for payment adjustments of asphalt materials; except no payment adjustment will be made for contract pay items under Subsection 510-01, "Pavement Patching", Section 507, "Asphaltic Surface Treatment", nor for any emulsions of cutbacks.

Item 510-02, Pavement Widening, and all contract pay items under Sections 502 and 508, will be eligible for payment adjustments of asphalt materials. No payment adjustment will be made for other asphalt materials, including emulsions and cutbacks.

The base price indices for asphalt cements and fuels will be posted on the DOTD internet website before the 10<sup>th</sup> calendar day of each month at the following URL: <a href="https://www.dotd.louisjana.gov/lettings/lac\_price\_index/priceindices.asp">www.dotd.louisjana.gov/lettings/lac\_price\_index/priceindices.asp</a>.

(c) Fuels: The base price index for this project will be the monthly price index in effect when bids are opened for the project. The monthly price index will be the minimum price quotations for unleaded gasoline and No. 2 diesel fuel listed for the New Orleans area in *Platt's Oilgram and Price Report* effective on the first calendar day of each month.

Payment adjustment will be made in accordance with the following formulas:

If Monthly Price Index exceeds Base Price Index,  

$$P_a = (A - 1.05B) \times Q \times F$$

If Base Price Index exceeds Monthly Price Index,  

$$P_a = (0.95B - A) \times Q \times F$$

Where:

 $P_a$  = Price adjustment.

A = Monthly Price Index in dollars per gallon/liter.

B = Base Price Index in dollars per gallon/liter.

Q = Pay Item Quantity (Pay Units).

F = Fuel Usage Factor Gal (L)/Pay Unit.

The following is a listing of contract pay items that are eligible for payment adjustment and the fuel usage factors that will be used in making such adjustment. Contract items that

expand the items listed herein by use of letter or number designations are also eligible for fuel price adjustments; for example:

Item 601-01-G, Portland Cement Concrete Pavement 8 inches (200 mm) thick.

# ELIGIBLE CONTRACT PAY ITEMS & FUEL USAGE FACTORS FOR FUEL PAYMENT ADJUSTMENT<sup>7</sup>

ITEM NO.	PAY ITEM	UNITS	MIN. ORIGINAL CONTRACT	FUEL USAG	E FACTORS
			QUANTITY FOR PAY ADJUSTMENT	Diesel <sup>2</sup>	Gasoline
203-01	General Excavation	gal/cu yd	10,000 cu yd	0.29	0.15
203-02	Drainage Excavation	gal/cu yd	10,000 cu yd	0.29	0.15
203-03 <sup>1</sup>	Embankment	gal/cu yd	10,000 cu yd	0.29	0.15
203-04	Nonplastic Embankment	gal/cu yd	10,000 cu yd	0.29	0.15
203-07	Borrow (Vehicular Measurement)	gal/cu yd	10,000 cu yd	0.29	0.15
301-01	Class I Base Course	gal/cu yd	3,000 cu yd	0.88	0.57
301-02	Class I Base Course ( " Thick)	gal/sq yd	50,000 sq yd	0.04	0.03
302-01	Class II Base Course	gal/cu yd	3,000 cu yd	0.88	0.57
302-02	Class II Base Course ( " Thick)	gal/sq yd	50,000 sq yd	0.04	0.03
303-01	In-Place Cement Stabilized Base Course	gal/sq yd	50,000 sq yd	0.04	0.03
304-02	Lime Treatment (Type B)	gal/sq yd	50,000 sq yd	0.04	0.03
304-03	Lime Treatment (Type C)	gal/sq yd	50,000 sq yd	0.04	0.03
304-04	Lime Treatment (Type D)	gal/sq yd	50,000 sq yd	0.04	0.03
305-01	Subgrade Layer ( " Thick)	gal/sq yd	50,000 sq yd	0.04	0.03
308-01	In-Place Cement Treated Base Course	gal/sq yd	50,000 sq yd	0.04	0.03
401-01	Aggregate Surface Course (Net Section)	gal/cu yd	3,000 cu yd	0.88	0.57
401-02	Aggregate Surface Course (Adjusted Vehicular Measurement)	gal/cu yd	3,000 cu yd	0.88	0.57
502-01	Superpave Asphaltic Concrete	gal/ton	1000 ton	$2.40^{3}$	0.2
502-02	Superpave Asphaltic Concrete	gal/cu yd	500 cu yd	4.80 <sup>4</sup>	0.4
502-03	Superpave Asphaltic Concrete ( "Thick)	gal/sq yd	10,000 sq yd	0.13 <sup>5,6</sup>	0.016
508-01	Asphaltic Concrete (SMA)	gal/ton	1000 ton	$2.40^{3}$	0.2
510-02	Pavement Widening	gal/sq yd	3,000 sq yd	0.86	0.24
601-01	Portland Cement Concrete Pavement ( "Thick)	gal/sq yd	15,000 sq yd	0.11	0.15

<sup>1</sup> If project has both 203-01 & 203-03, only the item with larger quantity is eligible.

For fuel adjustment purposes, the term "diesel" shall represent No. 2 or No. 4 fuel oils or any of the liquified petroleum gases, such as propane or butane.

<sup>3</sup> If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 1.67 gal/ton.

<sup>4</sup> If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 13.34 gal/cu yd.

<sup>5</sup> If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 0.09 gal/sq yd.

<sup>6</sup> Per inch of thickness.

<sup>7</sup> No fuel adjustment will be allowed for waste oil.

ELIGIBLE CONTRACT PAY ITEMS & FUEL USAGE FACTORS FOR FUEL PAYMENT ADJUSTMENT (METRIC)<sup>7</sup>

			<del>- \                                   </del>		
ITEM NO.	PAY ITEM	UNITS	MIN. ORIGINAL CONTRACT QUANTITY FOR PAY ADJUSTMENT	FUEL USAG	E FACTORS  Gasoline
203-011	General Excavation	l/m³	7,600 m <sup>3</sup>	1.44	0.74
203-02	Drainage Excavation	1/m³	7,600 m <sup>3</sup>	1.44	0.74
203-03 <sup>1</sup>	Embankment	l/m³	7,600 m <sup>3</sup>	1.44	0.74
203-04	Nonplastic Embankment	l/m³	7,600 m <sup>3</sup>	1.44	0.74
203-07	Borrow (Vehicular Measurement)	I/m³	7,600 m <sup>3</sup>	1.44	0.74
301-01	Class I Base Course	l/m³	2,300 m <sup>3</sup>	4.36	2.82
301-02	Class I Base Course ( mm Thick)	l/m²	41,800 m <sup>2</sup>	0.18	0.14
302-01	Class II Base Course	l/m³	2,300 m <sup>3</sup>	4.36	2.82
302-02	Class II Base Course ( mm Thick)	l/m²	41,800 m <sup>2</sup>	0.18	0.14
303-01	In-Place Cement Stabilized Base Course	1/m <sup>2</sup>	41,800 m <sup>2</sup>	0.18	0.14
304-02	Lime Treatment (Type B)	l/m²	41,800 m <sup>2</sup>	0.18	0.14
304-03	Lime Treatment (Type C)	l/m²	41,800 m <sup>2</sup>	0.18	0.14
304-04	Lime Treatment (Type D)	l/m <sup>2</sup>	41,800 m <sup>2</sup>	0.18	0.14
305-01	Subgrade Layer ( mm Thick)	1/m <sup>2</sup>	41,800 m <sup>2</sup>	0.18	0.14
308-01	In-Place Cement Stabilized Base Course	l/m²	41,800 m <sup>2</sup>	0.18	0.14
401-01	Aggregate Surface Course (Net Section)	l/m <sup>3</sup>	2,300 m <sup>3</sup>	4.36	2.82
401-02	Aggregate Surface Course (Adjusted Vehicular Measurement)	l/m³	2,300 m <sup>3</sup>	4.36	2.82
502-01	Superpave Asphaltic Concrete	l/Mg	900 Mg	10.013	0.83
502-02	Superpave Asphaltic Concrete	l/m³	400 m <sup>3</sup>	23.774	1.98
502-03	Superpave Asphaltic Concrete ( mm Thick)	l/m²	8,400 m <sup>2</sup>	0.59 <sup>5,6</sup>	0.456
508-01	Asphaltic Concrete (SMA)	l/Mg	900 Mg	10.013	0.83
510-02	Pavement Widening	l/m <sup>2</sup>	2,500 m <sup>2</sup>	3.89	1.09
601-01	Portland Cement Concrete Pavement ( mm Thick)	l/m²	12,500 m <sup>2</sup>	0.5	0.68

If project has both 203-01 & 203-03, only the item with larger quantity is eligible.

<sup>2</sup> For fuel adjustment purposes, the term "diesel" shall represent No. 2 or No. 4 fuel oils or any of the liquified petroleum gases, such as propane or butane.

If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 6.97 l/mg. If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 16.53 l/m<sup>3</sup>.

If natural gas or coal is used instead of diesel for aggregate drying and heating the fuel usage factor shall be 0.41 l/m<sup>2</sup>.

Per mm of thickness.

No fuel adjustment will be allowed for waste oil.

SUPERPAVE ASPHALTIC CONCRETE MIXTURES (11/08): Section 502, Superpave Asphaltic Concrete Mixtures of the 2006 Standard Specifications as amended by the supplemental specifications thereto, is further amended as follows.

Subsection 502.04, Job Mix Formula Validation.

Delete the first sentence of the sixth paragraph and substitute the following.

A JMF is considered validated if the following parameters are 71 percent within limits of the JMF and meet the specifications requirements.

Subsection 502.05, Plant Quality Control.

Delete the first paragraph and substitute the following.

For quality control purposes, the contractor shall obtain a minimum of two (2) samples of mixture from each sublot using a stratified random sampling approach. Test results for theoretical maximum specific gravity (G<sub>mm</sub>) and measured bulk specific gravity (G<sub>mb</sub>) at N<sub>max</sub> and percent G<sub>mm</sub> at N<sub>initial</sub>, on samples of each sublot shall be reported. Control charts may be requested by the engineer if mixture problems develop. Quality control gyratory samples may be aged or unaged at the contractor's option, but the method chosen shall be used consistently throughout the project. If aged samples are used, report the measured Gmb at Nmax. If unaged samples are used, report the estimated Gmb at Nmax. One loose mix sample shall be taken from each sublot after placement of the mix in the truck. The mix shall be tested by the contractor at the plant for aggregate gradation, asphalt content and percent crushed aggregate. The mix shall be tested in accordance with DOTD TR 309, TR 323 and TR 306. The lot average and standard deviation shall be determined for aggregate gradation and asphalt content. The percent within limits (PWL) shall be determined on the Nos. 8 and 200 (2.36 mm and 75 µm) sieves and for G<sub>mm</sub>. Corrective action shall be taken if these parameters fall below 71 PWL. For each lot, the contractor shall report all quality control data to the DOTD Certified Plant Technician. The full range of gradation mix tolerances will be allowed even if they fall outside the control points. The District Laboratory Engineer may require re-validation of the mix when the average of the Quality Control data indicates non-compliance with the specified limits or tolerances.

Subsection 502.15, Measurement.

Subheading (c), Surface Tolerance Incentive Measurement.

Delete the first paragraph and substitute the following.

At the completion of construction of the project, an independent certified profiler such as that of a private company or the Materials and Testing Section, approved by the Department, shall be used to measure a continuous profile from the start station to the end station of the construction project for the purpose of determining qualification for incentive pay under Subsection 502.16(e). Bridges and 300 feet (90 m) on each end of the bridge will be excluded from measurements for surface tolerance incentive pay.

Delete Table 502-7A, Payment Adjustment Schedule for Plant Acceptance and substitute the following.

Table 502-7A
Payment Adjustment Schedule for Plant Acceptance

r dyment rajuestiont conceder for i funt recoptance		
Air Voids PWL (90 AQL.)	Percent Payment	
71-100	100	
61-70	90	
51-60	80	
≤50	50 or Remove <sup>1</sup>	

<sup>&</sup>lt;sup>1</sup>At the option of the Department after investigation.

Delete Table 502-7B, Payment Adjustment Schedule for Roadway Density and substitute the following.

Table 502-7B
Payment Adjustment Schedule for Roadway Density

t ay interior transport of the contract to the transport of the contract of th		
Roadway Density PWL (90 AQL)	sity PWL (90 AQL) Percent Payment	
99-100	00 102	
81-98	100	
71-80	95	
51-70	80	
≤50	50 or Remove <sup>1</sup>	

<sup>&</sup>lt;sup>1</sup>At the option of the Department after investigation.

Delete Table 502-8A, Payment Adjustment Schedules for Longitudinal Surface Tolerance, Maximum International Roughness Index, inches per mile (mm per km) and substitute the following.

#### **Table 502-8A**

Payment Adjustment Schedules for Longitudinal Surface Tolerance, Maximum International Roughness Index,

inches per mile (mm per km) Percent of Contract Unit 50% or 102%<sup>2</sup> Price (by Sublot)<sup>1</sup> 100% 90% 80% Remove<sup>3</sup> Category A Interstates, All <45 65-75 Multi-Lift New <65 >75 NA Construction and Overlays of More (1030-1180) (<710)(<1030)(>1180)than two Lifts Category B One or Two Lift Overlays Over Cold <55 <75 75-89 >89 NA Planed Surfaces, and Two-Lift (<870) (<1180) | (1180-1400) (>1400)Overlays Over Existing Surfaces<sup>4</sup> Category C <85 85-95 >95-110 >110 Single-Lift Overlays Over Existing N/A (1340-1500) (>1500-1740) (<1340) (>1740)Surfaces<sup>4</sup> Longitudinal Surface Tolerance Incentive Pay, Final Completion, ≤ 45 (≤ 710) Average of All Travel Lanes<sup>5</sup>

Delete Table 502-8B, Individual Wheelpath Deficient Area Limits, Maximum International Roughness Index, Inches per Mile (mm per km) and substitute the following.

Table 502-8B
Individual Wheelpath Deficient Area Limits
Maximum International Roughness Index, inches per mile (mm per km)

Any 0.05 Mile (0.08 km) Segment	Wearing Course	Binder Course
Category A	89 (1400)	130 (2050)
Category B	99 (1560)	150 (2370)
Category C	N/A	N/A

PLASTIC PAVEMENT MARKINGS (09/07): Section 732 of the 2006 Standard Specifications and the supplemental specifications thereto, is amended as follows.

Subsection 732.03, Construction Requirements for Plastic Pavement Marking Material.

Heading (a) is amended as follows.

The first paragraph is deleted and the following substituted.

(a) Equipment for Standard (Flat) Thermoplastic Marking Material: The application equipment shall consist of an extrusion die or a ribbon gun that simultaneously deposits and

Or portion of sublot placed on the project.

<sup>&</sup>lt;sup>2</sup>Maximum payment for sublots with exception areas, exclusions or grinding is 100 percent, unless the excluded area is a bridge end.

<sup>&</sup>lt;sup>3</sup>At the option of the engineer.

Existing surfaces include reconstructed bases without profile grade control.

<sup>&</sup>lt;sup>5</sup>Only Category A projects are eligible for incentive. However, any grinding except within 300 feet (90 m) of a bridge end will cause the roadway to be ineligible for surface tolerance incentive pay. Measurements must be verified by an independent entity.

shapes lines at a thickness of 90 mils (2.3 mm) or greater on the pavement surface. When restriping onto existing thermoplastic markings, only a ribbon gun shall be used. Finished

markings shall be continuous and uniform in shape, and have clear and sharp dimensions. Applicators shall be capable of producing various widths of traffic markings. Applicators shall produce sharply defined lines and provide means for cleanly cutting off stripe ends and applying broken lines. The ribbon extrusion die or shaping die shall not be more than 2 inches (50 mm) above the roadway surface during application. A spray application will only be allowed when applying 40 mil (1.0 mm) thermoplastic.

Heading (e) is deleted and the following substituted.

(e) Application of Surface Primer: A single component surface primer will be required prior to placement of preformed plastic markings over an existing painted stripe, over oxidized asphalt, or when striping over existing thermoplastic on portland cement concrete surfaces unless otherwise directed by the engineer. A two component epoxy primer sealer will be required prior to placement of thermoplastic materials on portland cement concrete surfaces unless otherwise directed by the engineer.

SURFACE PREPARATION (07/04) (NS 500): This item consists of preparing the existing surfaces for single lift overlays.

Surface tolerances on single-lift overlays over existing surfaces shall be in accordance with Section 502 of the Standard Specifications. The contractor has the option of leveling, grinding, cold planing certain areas, or cold planing the entire project in order to meet surface tolerances. The contractor shall not cold plane more than 1/2 inch (13 mm) (average) from the existing surface. The contractor may retain 100 percent of the reclaimed asphaltic pavement (RAP).

Payment will be made under:

Item No.Pay ItemPay UnitNS-500-00280Surface PreparationLump Sum

SAW CUTTING ASPHALTIC CONCRETE PAVEMENT (05/08) (NS 500): This item consists of furnishing all equipment, labor, materials and incidentals to perform saw cutting of existing asphaltic concrete pavement at locations as shown on the plans or directed by the Project Engineer.

The saw cutting will be measured and paid at the contract unit price per inch depth of cut times the linear foot of cut.

Payment will be made at the contract unit price under:

Item No.Pay ItemPay UnitNS-500-00340Saw Cutting Asphaltic Concrete PavementPer Inch Depth-<br/>Linear Foot (per<br/>mm depth lin m)

CONTRACT TIME (03/05): The entire contract shall be completed in all details and ready for final acceptance in accordance with Subsection 105.17(b) within TWENTY FIVE (25) WORKING DAYS.

# LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT SUPPLEMENTAL SPECIFICATIONS

(FOR 2006 STANDARD SPECIFICATIONS)

#### TABLE OF CONTENTS

#### PART I – GENERAL PROVISIONS

SECTION 101 – GENERAL INFORMATION, DEFINITIONS, AND TERMS	
Subsection 101.03 – Definitions	I
SECTION 102 – BIDDING REQUIREMENTS	
Subsection 102.09 - Proposal / Bid Guaranty	1
SECTION 107 – LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC	
Subsection 107.05 – Federal Aid Participation	2
SECTION 108 – PROSECUTION AND PROGRESS	
Subsection 108.04 – Prosecution of Work	2
PART II – EARTHWORK	
SECTION 202 – REMOVING OR RELOCATING	
STRUCTURES AND OBSTRUCTIONS	
Subsection 202.06 – Plugging or Relocating Existing Water Wells	2
PART III – BASE COURSES	
SECTION 302 – CLASS II BASE COURSE	
Subsection 302.05 - Mixing	2
SECTION 305 – SUBGRADE LAYER	
Subsection 305.06 – Payment	2
SECTION 307 – PERMEABLE BASES	_
Subsection 307.02 - Materials	3
SECTION 308 – IN-PLACE CEMENT TREATED BASE COURSE	_
All Subsections	3
PART V – ASPHALTIC PAVEMENTS	
SECTION 502 – SUPERPAVE ASPHALTIC CONCRETE MIXTURES	
Subsection 502.02 - Materials	
Subsection 502.14 – Lot Sizes	4
SECTION 508 – STONE MATRIX ASPHALT	
Subsection 508.01 – Description	
Subsection 508.02 - Materials	5

Supplemental Specifications – Table of Contents (08/08)
PART VI – RIGID PAVEMENT
SECTION 602 PORTLAND CEMENT CONCRETE PAVEMENT REHABILITATION
Subsection 602.17 – Payment5
PART VII – INCIDENTAL CONSTRUCTION
SECTION 701 – CULVERTS AND STORM DRAINS
All Subsections5
SECTION 704 – GUARD RAIL
Subsection 704.03 – General Construction Requirements
All Subsections16
SECTION 713 – TEMPORARY TRAFFIC CONTROL
Subsection 713.06 – Pavement Markings
SECTION 729 - TRAFFIC SIGNS AND DEVICES
Subsection 729.02 – Materials
PART VIII – STRUCTURES
SECTION 804 – DRIVEN PILES
Subsection 804.08 - Construction Requirements
PART IX – PORTLAND CEMENT CONCRETE
SECTION 901 – PORTLAND CEMENT CONCRETE
Subsection 901.06 – Quality Control of Concrete
Subsection 901.08 – Composition of Concrete
PART X – MATERIALS
SECTION 1001 – HYDRAULIC CEMENT
Subsection 1001.01 – Portland Cement
SECTION 1003 - AGGREGATES
Subsection 1003.02 – Aggregates for Portland Cement Concrete and Mortar
SECTION 1005 – JOINT MATERIALS FOR PAVEMENTS AND STRUCTURES Subsection 1005.04 – Combination Joint Former/Sealer
SECTION 1006 – CONCRETE AND PLASTIC PIPE
Subsection 1006.09 – Plastic Yard Drain Pipe23
F_2

### Supplemental Specifications - Table of Contents (08/08)

SECTION 1013 – METALS	
Subsection 1013.09 - Steel Piles	23
SECTION 1015 – SIGNS AND PAVEMENT MARKINGS	
Subsection 1015.04 – Sign Panels	23
Subsection 1015.05 - Reflective Sheeting	
Subsection 1015.11 - Preformed Plastic Pavement Marking Tape	
SECTION 1020 – TRAFFIC SIGNALS	
Subsection 1020.01 - Traffic Signal Heads	29
Subsection 1020.04 – Poles for Traffic Signal Systems	

# LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT SUPPLEMENTAL SPECIFICATIONS

The 2006 Louisiana Standard Specifications for Roads and Bridges and supplemental specifications thereto are amended as follows.

#### PART I – GENERAL PROVISIONS

#### SECTION 101 – GENERAL INFORMATION, DEFINITIONS, AND TERMS:

Subsection 101.03 – Definitions (07/07), Pages 3 - 13).

Delete the definition for "Proposal/Bid Guaranty" and substitute the following.

Proposal / Bid Guaranty. The required security furnished with a bid. The only form of security acceptable is a Bid Bond.

#### **SECTION 102 – BIDDING REQUIREMENTS:**

Subsection 102.09 - Proposal / Bid Guaranty (07/07), Page 19.

Delete the contents of this subsection and substitute the following.

PROPOSAL/BID GUARANTY. Each bid shall be accompanied by a proposal/bid guaranty in an amount not less than five percent of the total bid amount when the bidder's total bid amount as calculated by the Department in accordance with Subsection 103.01 is greater than \$50,000. No proposal/bid guaranty is required for projects when the bidder's total bid amount as calculated by the Department is \$50,000 or less. The official total bid amount for projects that include alternates is the total of the bidder's base bid and all alternates bid on and accepted by the Department. The proposal/bid guaranty submitted by the bidder shall be a bid bond made payable to the contracting agency as specified on the bid bond form provided in the construction proposal. No other form of security will be accepted.

The bid bond shall be on the "Bid Bond" form provided in the construction proposal, on a form that is materially the same in all respects to the "Bid Bond" form provided, or on an electronic form that has received Department approval prior to submission. The bid bond shall be filled in completely, shall be signed by an authorized officer, owner or partner of the bidding entity, or each entity representing a joint venture; shall be signed by the surety's agent or attorney-in-fact; and shall be accompanied by a notarized document granting general power of attorney to the surety's signer. The bid bond shall not contain any provisions that limit the face amount of the bond.

The bid bond will be written by a surety or insurance company that is in good standing and currently licensed to write surety bonds in the State of Louisiana by the Louisiana Department of Insurance and also conform to the requirements of LSA-R.S. 48:253.

All signatures required on the bid bond may be original, mechanical reproductions, facsimiles or electronic. Electronic bonds issued in conjunction with electronic bids must have written Departmental approval prior to use. The Department will make a listing of approved electronic sureties providers on the Bidx.com site.

### Supplemental Specifications (August 2008) Page 2 of 30

#### SECTION 107 – LEGAL RELATIONS AND RESPONSIBILITY TO PUBLIC:

Subsection 107.05 - Federal Aid Participation (04/08), Pages 57 and 58.

Delete the second paragraph.

#### **SECTION 108 – PROSECUTION AND PROGRESS:**

Subsection 108.04 - Prosecution of Work (03/05) Pages 74 and 75.

Add the following sentence to the third paragraph of Heading (b).

Should the surety or the Department take over prosecution of the work, the contractor shall remain disqualified for a period of one year from the completion of the project, unless debarment proceedings are instituted.

When the Department of Transportation and Development is not the contracting agency on the project, the second paragraph under Heading (c) is deleted.

#### PART II – EARTHWORK

### SECTION 202 – REMOVING OR RELOCATING STRUCTURES AND OBSTRUCTIONS:

<u>Subsection 202.06 – Plugging or Relocating Existing Water Wells (03/04), Page 105.</u>

Delete the first sentence and substitute the following.

All abandoned wells shall be plugged and sealed at the locations shown on the plans, or as directed by the engineer, in accordance with the "Water Well Rules, Regulations, and Standards, State of Louisiana." This document is available at the Department of Transportation and Development, Water Resources Section, P. O. Box 94245, Baton Rouge, Louisiana 70804-9245. The Water Resource Section's telephone number is (225) 274-4172.

#### PART III – BASE COURSES

#### **SECTION 302 – CLASS II BASE COURSE:**

<u>Subsection 302.05 – Mixing (08/06), Pages 152 and 153.</u>

Delete the first sentence of Subheading (b)(1), In-Place Mixing, and substitute the following.

In-place mixing shall conform to Heading (a)(1) except that the percentage of Type I portland cement required will be 6 percent by volume.

#### **SECTION 305 – SUBGRADE LAYER:**

Subsection 305.06 – Payment (01/08), Page 184.

Delete the contents of this subsection and substitute the following.

305.06 Payment. Payment for subgrade layer will be made at the contract unit price which includes lime, lime treatment, cement, cement treatment, water, stone, recycled portland cement concrete, crushed slag, blended calcium sulfate, asphaltic concrete, and asphalt curing membrane or prime coat, subject to the payment adjustment provisions of Section 1002 for specification deviations of asphalt materials and Subsection 303.11(a) for density deficiencies of cement treated materials. Adjustments in pay for increase or decrease in the percent cement ordered by the engineer will be in accordance with Subsection 303.13. Adjustments in pay for

### Supplemental Specifications (August 2008) Page 3 of 30

increase or decrease in the percent lime ordered by the engineer will be based on the price of lime shown on paid invoices (total of all charges). The Materials and Testing Section will provide the payment adjustment percentage for properties of asphalt materials.

Payment for geotextile fabric will be included in the contract unit price for subgrade layer.

Payment will be made under:

Item No.Pay ItemPay Unit305-01Subgrade Layer \_\_\_\_in (mm) ThickSquare Yard (Sq m)

#### **SECTION 307 – PERMEABLE BASES:**

Subsection 307.02 - Materials (09/07), Pages 187 and 188.

Delete the contents of Subheading (b), Asphalt, and substitute the following.

(b) Asphalt: The asphalt for asphalt treated permeable base shall be an approved polymer modified asphalt cement, PG 76-22m, or PG 82-22rm complying with Section 1002. The percentage of asphalt cement shall be 2.0 percent to 4.0 percent by weight (mass) of the total mixture. Asphalt cement content and mixing process shall be such that all aggregates are visibly coated. The mixture shall retain 90 percent coating when tested in accordance with DOTD TR 317.

A job mix formula shall be submitted and approved in accordance with Section 502.

#### **SECTION 308 – IN-PLACE CEMENT TREATED BASE COURSE:**

All Subsections within Section 308 – (07/07), Pages 191 – 198.

Whenever the reference to "DOTD TR-432, Method D" is used, it shall mean "DOTD TR-432".

#### PART V – ASPHALTIC PAVEMENTS

#### SECTION 502 – SUPERPAVE ASPHALTIC CONCRETE MIXTURES:

Subsection 502.02 – Materials (08/06) (11/07), Pages 210 – 213.

<u>Delete Table 502-2, Superpave Asphalt Cement Usage under Subheading (a) and substitute the following.</u>

# Supplemental Specifications (August 2008) Page 4 of 30

Table 502-2 Superpave Asphalt Cement Usage

Current Traffic Load Level	Mixture Type	Grade of Asphalt Cement
	Wearing Course	PG 70-22m
Level I	Binder Course	PG 70-22m
	Base Course	PG 64-22
Level 2	Wearing Course	PG 76-22m
Level 2	Binder Course	PG 76-22m
Level A	Incidental Paving	PG 70-22m

Note: A PG 82-22 rm, Waste Tire Rubber Modified Asphalt, may be substituted for any other grade of asphalt cement.

Delete Table 502-3, Aggregate Friction Rating under Subheading (c)(1) and substitute the following.

Table 502-3 Aggregate Friction Rating

Friction Rating	on Rating Allowable Usage		
I	All mixtures		
II	All mixtures		
III	All mixtures, except travel lane wearing courses with plan ADT greater than 7000 <sup>1</sup>		
IV	All mixtures, except travel lane wearing courses <sup>2</sup>		

<sup>&</sup>lt;sup>1</sup> When plan current average daily traffic (ADT) is greater than 7000, blending of Friction Rating III aggregates and Friction Rating I and/or II aggregates will be allowed for travel lane wearing courses at the following percentages. At least 30 percent by weight (mass) of the total aggregates shall have a Friction Rating of I, or at least 50 percent by weight (mass) of the total aggregate shall have a Friction Rating of II. The frictional aggregates used to obtain the required percentages shall not have more than 10 percent passing the No. 8 (2.36 mm) sieve.

#### Subsection 502.14 – Lot Sizes (11/07), Pages 232 and 233.

Delete the first sentence of the first paragraph and substitute the following.

<sup>&</sup>lt;sup>2</sup> When the average daily traffic (ADT) is less than 2500, blending of Friction Rating IV aggregates with Friction Rating I and/or II aggregates will be allowed for travel lane wearing courses at the following percentages. At least 50 percent by weight (mass) of the total aggregate in the mixture shall have a Friction Rating of I or II. The frictional aggregates used to obtain the required percentages shall not have more than 10 percent passing the No. 8 (2.36 mm) sieve.

A lot is a segment of continuous production of asphaltic concrete mixture from the same job mix formula produced for the Department at a specific plant, delivered to a specific DOTD project.

#### SECTION 508 – STONE MATRIX ASPHALT:

Subsection 508.01 – Description (09/07), Page 274.

Delete this subsection and substitute the following.

508.01 DESCRIPTION. This work consists of furnishing and constructing Stone Matrix Asphalt (SMA) which is a plant mixed asphalt concrete wearing course for high traffic applications. This mixture is a rut resistant hot mix design with stone on stone contact. The mixture shall be composed of a PG 76-22m, or PG 82-22rm asphalt cement and a gap graded coarse aggregate structure. Mineral filler and/or fibers shall be used to control draindown. This work shall be in accordance with these specifications, plan details, and as directed. All requirements of Section 502 apply to Stone Matrix Asphalt, except as modified herein. All plant and paving equipment and processes must meet the requirements of Section 503.

Mixture used for shoulder may be Stone Matrix Asphalt or any mixture type shown in Table 502-5.

#### <u>Subsection 508.02 – Materials (09/07)</u>, Page 274.

Delete the contents of subheading (a), Asphalt Cement and substitute the following.

(a) Asphalt Cement: Asphalt cement shall be PG 76-22m, or PG 82-22rm as listed on QPL 41 and complying with Section 1002.

#### PART VI – RIGID PAVEMENT

### SECTION 602 – PORTLAND CEMENT CONCRETE PAVEMENT REHABILITATION:

<u>Subsection 602.17 – Payment (09/07)</u>, Pages 341 – 344.

Delete the last paragraph of Subheadings (d), Full Depth Corner Patching of Jointed Concrete Pavement, (e) Full Depth Patching of Jointed Concrete Pavement, and (g) Patching Continuously Reinforced Concrete Pavement, and substitute the following.

Payment for deteriorated base course removed as directed by the engineer and replaced with concrete will be made as follows: The value per inch (mm) thickness will be determined by dividing the contract unit price per square yard (sq m) by the plan thickness. Thickness of patches will be measured from the surface that exists at the time of patching. Payment for the additional thickness will be made at 50 percent of the value per inch (mm) thus determined.

#### PART VII – INCIDENTAL CONSTRUCTION

#### **SECTION 701 – CULVERTS AND STORM DRAINS:**

All Subsections within Section 701 (08/07), Pages 347 - 358.

Delete Section 701, Culverts and Storm Drains and substitute the following.

## Supplemental Specifications (August 2008) Page 6 of 30

#### SECTION 701 CULVERTS AND STORM DRAINS

701.01 DESCRIPTION. This work consists of furnishing, installing, and cleaning pipe, pipe arch, storm drains and sewers, also referred to as culverts or conduit, in accordance with these specifications and in conformity with lines and grades shown on the plans or established.

701.02 MATERIALS. Materials shall comply with the following sections and subsections:

Usable Soil	203.06(a)
Selected Soil	203.06(b)
Plastic Soil Blanket	203.10
Mortar	702.02
Flowable Fill	710
Portland Cement Concrete	901
Reclaimed Asphaltic Pavement (RAP)	1003.01 & 1003.04(d)
Stone	1003.03(b)
Recycled Portland Cement Concrete	1003.03(c)
Granular Material	1003.07
Bedding Material	1003.08
Concrete Sewer Pipe	1006.02
Reinforced Concrete Pipe	1006.03
Reinforced Concrete Pipe Arch	1006.04
Gasket Materials	1006.06
Plastic Pipe	1006.07
Split Plastic Coupling Bands	1006.07(d)(4)
Plastic Yard Drain Pipe	1006.09
Bituminous Coated Corrugated Steel Pipe and	
Pipe Arch	1007.02
Structural Plate for Pipe, Pipe Arch and Arch	1007.04
Corrugated Aluminum Pipe and Pipe Arch	1007.05
Coupling Bands	1007.09
Reinforcing Steel	1009
Geotextile Fabric	1019

- (a) Side Drain Pipe or Side Drain Pipe Arch: When the item for Side Drain Pipe or Side Drain Pipe Arch is included in the contract, the contractor has the option of furnishing reinforced concrete pipe or reinforced concrete pipe arch, corrugated metal pipe or corrugated metal pipe arch, or plastic pipe, as allowed by EDSM II.2.1.1 or unless otherwise specified.
- (b) Cross Drain Pipe or Cross Drain Pipe Arch: When the item for Cross Drain Pipe or Cross Drain Pipe Arch is included in the contract, the contractor has the option of furnishing reinforced concrete pipe or reinforced concrete pipe arch, corrugated metal pipe or corrugated metal pipe arch, or plastic pipe, as allowed by EDSM II.2.1.1 or unless otherwise specified.

- (c) Storm Drain Pipe or Storm Drain Pipe Arch: When the item for Storm Drain Pipe or Storm Drain Pipe Arch is included in the contract, the contractor has the option of furnishing reinforced concrete pipe or reinforced concrete pipe arch, or plastic pipe, as allowed by EDSM II.2.1.1 or unless otherwise specified.
- (d) Yard Drain Pipe: When the item for Yard Drain Pipe is included in the contract, the contractor has the option of furnishing concrete sewer pipe, plastic yard drain pipe or plastic pipe in accordance with Section 1006 unless otherwise specified.
  - (e) Material Type Abbreviations:
    - (1) Reinforced Concrete Pipe:

RCP Reinforced Concrete Pipe RCPA Reinforced Concrete Pipe Arch

(2) Corrugated Metal Pipe:

CAP Corrugated Aluminum Pipe CAPA Corrugated Aluminum Pipe Arch

CMP Corrugated Metal Pipe

CMPA Corrugated Metal Pipe Arch

CSP Corrugated Steel Pipe CSPA Corrugated Steel Pipe Arch

BCCSP Bituminous Coated Corrugated Steel Pipe
BCCSPA Bituminous Coated Corrugated Steel Pipe Arch

(3) Plastic Pipe:

PP Plastic Pipe

PVCP Polyvinyl Chloride Pipe

RPVCP Ribbed Polyvinyl Chloride Pipe

CPEPDW Corrugated Polyethylene Pipe Double Wall

(f) Joint Type Abbreviations:

T1 Type 1 Joint T2 Type 2 Joint T3 Type 3 Joint

(g) Quality Assurance for Pipe: Manufacturing plants will be periodically inspected for compliance with specified manufacturing methods, and material samples will be randomly obtained for laboratory testing for verification of manufacturing lots. Materials approved at the manufacturing plant will be subject to visual acceptance inspections at the jobsite or point of delivery.

701.03 EXCAVATION. For all pipe, when the sides of the trench are stable as evidenced by the sides of the trench being able to maintain a vertical cut face, the minimum trench width at the bottom of the excavation will be 18 inches (460mm) on either side of the outside diameter of the pipe. If the sides of the trench are unstable, the width of the trench at the bottom of the excavation, for plastic or metal pipe, shall be a minimum width of at least 18 inches (460mm) or one pipe diameter on each side of the outside diameter of the pipe, which ever is greater. Surplus material or excavated material that does not conform to the requirements of Subsection 203.06(a) shall be satisfactorily disposed of in accordance with Subsection 202.02. Moisture controls

## Supplemental Specifications (August 2008) Page 8 of 30

including backfill materials selection and dewatering using sumps, wells, well points or other approved processes may be necessary to control excess moisture during excavation, installation of bedding, over-excavated trench backfilling, pipe placement and pipe backfill.

(a) Over-excavation: When unsuitable soils as defined in Subsection 203.04 or a stable, non-yielding foundation cannot be obtained at the established pipe grade, or at the grade established for placement of the bedding, unstable or unsuitable soils below this grade shall be removed and replaced with granular material meeting the requirements of Subsection 1003.07, bedding materials meeting the requirements of Subsection 1003.08 or Type A backfill. All granular, backfill materials placed below the established pipe or bedding grade shall be placed in lifts not exceeding 8 inches (200 mm) thick and sufficiently compacted by hand or a dynamic mechanical hand compaction device over the surface of each lift to form a stable, non-yielding foundation at the surface of the established bedding or pipe grade.

When rock is encountered, it shall be removed below grade and replaced with material complying with Subsection 1003.07, bedding materials meeting the requirements of Subsection 1003.08 or Type A backfill. The compacted earth cushion shall have a thickness under the pipe of at least 1/2 inch per foot (40 mm/m) of fill height over the top of the pipe with a minimum thickness of 8 inches (200 mm). All granular, backfill materials placed below the established pipe or bedding grade shall be placed in lifts not exceeding 8 inches (200 mm) thick and sufficiently compacted by hand or a dynamic mechanical hand operated compaction device over the surface of each lift to form a stable, non-yielding foundation at the surface of the established bedding or pipe grade.

Materials used to backfill in an over-excavated portion of a trench do not require encasement in a Geotextile Fabric.

Density of approved materials placed in over-excavated trenches will not be measured or determined.

701.04 FORMING PIPE BED. Bedding material, when specified, shall be constructed in accordance with Section 726. Materials allowed for bedding shall be as specified in Subsection 1003.08 or may be Type A backfill materials. When bedding materials are specified, additional excavation shall be performed below established pipe grade and the bedding material placed in lifts not exceeding 8 inches (200 mm) thick and lightly compacted by hand or a dynamic hand compaction device over the surface of each lift.

When the bottom of the pipe is not laid in a trench but is constructed above natural soils, a uniform bed shall be constructed as specified for the bottom of a trench.

Density of approved bedding materials will not be measured or determined.

701.05 LAYING PIPE. Pipe laying shall begin at the downstream end of the line. The pipe shall be in contact with the foundation throughout its length. Bell or groove ends of pipe and outside circumferential laps of riveted metal pipe shall be placed facing upstream. Riveted seam metal pipe shall be placed with longitudinal laps at sides. Pipes in each continuous line shall have the same wall thickness. Metal pipes provided with lifting lugs shall be handled only by these lugs.

After pipe has been laid and before backfill is placed, the engineer will inspect the pipe for alignment, grade, integrity of joints, and coating damage.

#### 701.06 JOINING PIPE.

- (a) Joint Usage:
- (1) Type 1 (T1) joints shall be used for side drains under drives and similar installations.
- (2) Type 2 (T2) joints shall be used for cross drains under roadways, including turnouts.
- (3) Type 3 (T3) joints shall be used for closed storm drain systems, flumes and siphons.
- (b) Concrete Pipe: Concrete pipe may be either bell and spigot, or tongue and groove. The method of joining pipe sections shall be such that ends are fully entered and inner surfaces are flush and even.

An approved mechanical pipe puller shall be used for joining pipes over 36 inches (900 mm) in diameter. For pipe 36 inches (900 mm) or less in diameter, any approved method for joining pipe may be used which does not damage the pipe.

Joints shall comply with Subsection 1006.05, and shall be sealed with gasket material installed in accordance with the manufacturer's recommendations.

(c) Metal Pipe: Metal pipe shall be firmly joined by coupling bands. Bands shall be centered over the joint.

For Type 1 joints, approved gasket material shall be placed in one corrugation recess on each side of the joint at the coupling band and on each band connection in such manner to prevent leakage.

When Type 2 or 3 joints are specified, joining of metal pipe sections shall conform to the following provisions:

- (1) General: Band joints shall be sealed with gasket material. Gasket material shall be placed in accordance with the plan details.
- (2) Circular Section: Connecting bands shall be of an approved design and shall be installed in accordance with plan details.
- (3) Arch Section: Connecting bands shall be a minimum of 12 inches (300 mm) wide for pipe arch less than 36 inches (900 mm) round equivalent diameter, and a minimum of 21 inches (525 mm) wide for 36 inches (900 mm) round equivalent diameter pipe arch and greater. Bands shall be connected at the ends by approved angle or strap connections. Connecting bands used for 36 inches (900 mm) round equivalent diameter pipe arch and above shall be 2-piece bands.
- (d) Plastic Pipe: Joints for plastic pipe shall be either bell and spigot or split coupling bands.
- (1) Bell and Spigot Type Joint System: The method of joining pipe sections shall be such that ends are fully entered and inner surfaces are flush and even.

Any approved method for joining pipe may be used which does not damage the pipe.

Joints shall be approved and shall be sealed with a gasket system utilizing gasket material complying with Subsection 1006.06(a).

### Supplemental Specifications (August 2008) Page 10 of 30

(2) Split Coupling Type Joint System: Split coupling bands shall comply with all dimensional and material requirements of Subsection 1006.07. The bands shall be centered over the joint. The split coupling band shall be secured to the pipe with a minimum of five stainless steel or other approved corrosion resistant bands.

Joints shall be approved and shall be sealed with gasket material. Gasket material shall be placed in the first two corrugation recesses on each side of the pipe connections. Gasket material shall also be placed on each band connection to prevent leakage. When flexible plastic gasket material is used it shall be a minimum of 1/2 inch (13 mm) in size. The bands shall be tightened to create overlap of the band and shall adequately compress the gasket material.

- (e) Connections: Approved connections shall be used when joining new pipes to existing pipes. When concrete collars are required in order to extend the ends of existing pipes that have been damaged or to join different types or sizes of pipes, the concrete collars shall be constructed in accordance with plan details, the applicable requirements of Section 901, and as directed.
- (f) Geotextile Fabric, Pipe Joints: For concrete, metal and plastic pipes, Types 2 and 3 joints shall be wrapped with geotextile fabric for a minimum of 12 inches (300 mm) on each side of joint for pipe 36 inches (900 mm) or less in diameter and a minimum of 18 inches (450 mm) on each side of the joint for pipe greater than 36 inches (900 mm) in diameter. Ends of the fabric shall be lapped at least 10 inches (250 mm). The edges and ends of fabric shall be suitably secured for the entire circumference of the pipe.

701.07 RELAYING PIPE. If specified or directed, existing pipes shall be removed and suitable sections relaid as specified for new pipes.

#### 701.08 BACKFILLING.

(a) General: Prior to backfilling, pipes found to be damaged or out of alignment or grade shall be removed and reinstalled, or replaced.

Type A backfill material shall be stone, recycled portland cement concrete, flowable fill, or RAP.

Type B backfill materials are selected soils. Where Type B backfill materials are called for, Type A backfill materials may be substituted.

When corrugated metal pipe is used, the backfill material shall be tested and shall have a resistivity greater than 1500 ohm-cm and a pH greater than 5 when tested in accordance with DOTD TR 429 and DOTD TR 430 respectively.

When Type A backfill material is used, geotextile fabric surrounding this backfill shall be placed in accordance with Subsection 726.03 between the aggregate backfill material and all other natural or placed soils in the trench or embankment. Care shall be taken to prevent damage to geotextile fabric during placement of backfill material. For concrete pipe, the fabric shall enclose not only the initial backfill but shall be wrapped over the top of the pipe with at least 12 inches (300 mm) of overlap.

When a trench box or trench sheeting is used in unstable soils and/or for worker safety, and when moved during backfilling operations, filling and additional compaction of the disturbed zone of backfill must take place immediately and in a manner acceptable to the engineer.

Initial backfill is a structural backfill encasing the pipe from the bottom of the pipe to the springline for concrete pipe and to a point one foot (0.3 m) above the top of the pipe for both metal and plastic pipe. Final backfill is not a structural backfill and shall extend from the top of the initial backfill to the top of the natural ground or subgrade in cut areas or to the top of existing ground in fill areas. Any fill required above the final backfill is considered and treated as embankment.

- (b) Backfill Applications: For projects using A+B+C bidding method where rigid and flexible pavement alternates are considered, backfill application (2) below, "Cross Drains Under Flexible Pavements", shall apply for either rigid or flexible pavements.
- (1) Under Concrete Pavements: Type B backfill may be used as initial and final backfill for all pipes, culverts or drains under concrete pavements. Placement and compaction shall be as specified in Heading (d) below.
- (2) Cross Drains Under Flexible Pavements: All reaches, exclusive of those portions of the pipe which are under shoulders, of cross drains and all other culverts, pipes or drains that cross the centerlines of the new roadway or centerlines of existing roadways, such as intersections and are under flexible pavements shall receive an initial backfill of Type A material. Type B backfill materials may be used as final backfill for all pipes. Placement and compaction shall be as specified in Heading (c) and (d) below. Where the subgrade is above existing ground, embankment material as specified for the remainder of the project shall be used from the top of the final backfill to the top of the established embankment grade.
- (3) Other Drains Under Flexible Pavements: All reaches of all culverts, pipes or drains under flexible pavements that do not cross the centerlines of new roadway or centerlines of existing roadways, and exclusive of those portions of the pipe which are totally under shoulders, shall receive an initial and final backfill of Type B material. Placement and compaction shall be as specified in Heading (d) below. Where the subgrade is above existing ground, embankment material as specified for the remainder of the project shall be used from the top of the final backfill to the top of the established embankment grade.
- (4) Other Areas: All culverts, pipes or drains in nonpaved areas or paved areas that serve as driveways or shoulders shall receive an initial and final backfill of Type B material. Placement and compaction shall be as specified in Heading (d) below.
- (5) Pipes Subject to Construction Traffic; The embankment or pipe backfill shall be constructed to a minimum of 24 inches (600 mm) over the pipe before heavy construction equipment is allowed to cross the installation. Where practical, installations with less than 24 inches (600 mm) of cover over the top of the pipe shall be constructed after heavy hauling is completed over the pipe location. After completion of hauling operations, the contractor shall remove excess cover material. Pipe damaged by hauling and backfilling operations shall be removed and reinstalled, or replaced, at no direct pay.
- (c) Placement and Compaction; Type A Backfill: For all pipes, culverts and conduits under paved and nonpaved areas, where Type A backfill material is used, the Type A backfill shall be thoroughly hand compacted under the pipe haunches and then dynamically compacted in layers not exceeding 8 inches (200 mm) compacted thickness. Compaction under the haunches of the pipe shall initially be by hand tamping or other acceptable means, until a level is reached that the dynamic tamping can commence. Each lift shall be compacted by applying at least eight

### Supplemental Specifications (August 2008) Page 12 of 30

passes of a hand operated, dynamic mechanical compaction device over the surface of each lift. With approval of the engineer, layer thickness may be increased to 12 inches (300 mm) with verification of satisfactory installation and performance. If flowable fill is used it shall be furnished, placed and consolidated in accordance with Section 710. The contractor shall control placement operations during initial backfill operations so as not to damage protective coatings on metal pipes. The contractor shall repair damaged coatings at no additional pay.

- (d) Placement and Compaction; Type B Backfill: For all pipes, culverts and conduits, where Type B backfill is allowed, the Type B material shall be placed in layers not exceeding 8 inches (200 mm) compacted thickness. Compaction shall be with suitable mechanical equipment. With approval of the engineer, layer thickness may be increased to 12 inches (300 mm) with verification of satisfactory installation and performance.
- (e) Placement and Compaction; Trenchless or Partial Trench Condition: All pipes, culverts, drains and conduits placed with any portion of the pipe above existing ground must also comply with Subsections (a),(b) (c) and (d) above for the portion of the pipe within a trench and that portion of the pipe not constructed in a trench. The width of initial and final backfill of that portion above existing ground and not within a trench will be constructed to such a width that the requirements for placement, compaction and density are met.
- (f) Density Requirements: The in place density of Type A backfill materials and bedding materials, will not be measured or determined. Type A backfill, exclusive of RAP and flowable fill, shall be placed at or near optimum moisture content determined in accordance with DOTD TR 415 or 418. RAP materials shall be placed and compacted in a slightly moist condition.

The maximum dry density of initial or final Type B backfill under all paved areas which are to be under traffic will be determined in accordance with DOTD TR 415 or TR 418 and inplace density determined in accordance with DOTD TR 401. Initial and final Type B backfill under all paved areas, under traffic, shall be placed at or near optimum moisture content determined in accordance with DOTD TR 415 or TR 418. Each layer shall be compacted by approved methods prior to the placement of a subsequent layer. The engineer will approve the compaction method based upon validation that such method, including moisture control, will achieve at least 95 percent of maximum dry density as determined in accordance with DOTD TR 401. With approval of the engineer, density testing may be waived on subsequent layers with backfill installation in accordance with approved compaction methods and continued satisfactory performance.

Initial and final backfill in unpaved areas or paved areas such as shoulders or driveways, shall be placed evenly and compacted along the length of the culvert, pipe or drain from the top of the initial backfill to the top of the subgrade. Layered backfill shall be compacted at least to the density of the adjoining existing soils or the compaction required of the laterally adjoining layers of soil immediately outside the trench for embankment elevations. Initial and final backfill shall be placed and compacted at or near optimum moisture content determined in accordance with DOTD TR 415 or TR 418.

701.09 INSPECTION OF PIPES. After completion of embankment and prior to roadway surfacing, the engineer shall inspect pipes for proper alignment and integrity of joints. Any misaligned pipe or defective joints shall be corrected by the contractor at no direct pay.

(a) Plastic Pipe: Installed plastic pipe shall be tested to ensure that vertical deflections do not exceed 5.0 percent. Maximum allowable deflections shall be governed by the mandrel requirements stated herein.

Deflection tests shall be performed no sooner than 30 calendar days after installation and compaction of backfill. The pipe shall be cleaned and inspected for offsets and obstructions prior to testing.

For pipe 36 inches (900 mm) and less in diameter, a mandrel shall be pulled through the pipe by hand to ensure that maximum allowable deflections have not been exceeded. The mandrel shall be approved by the engineer prior to use. Use of an unapproved mandrel or a mandrel altered or modified after approval will invalidate the test. If the mandrel fails to pass, the pipe is overdeflected.

Unless otherwise permitted, overdeflected pipe shall be uncovered and, if not damaged, reinstalled. Damaged pipe shall not be reinstalled, but shall be removed and replaced with new pipe. Any pipe subjected to any method or process other than removal, which attempts, even successfully, to reduce or cure any overdeflection, shall be removed and replaced with new pipe.

The mandrel shall be a rigid, nonadjustable, odd-numbered legged (minimum 9 legs) mandrel having a length not less than its nominal diameter or 24 inches (600 mm), whichever is less. The minimum diameter at any point shall be 5.0 percent less than the base inside diameter of the pipe being tested. The mandrel shall be fabricated of steel, aluminum or other approved material fitted with pulling rings at each end. The nominal pipe size and outside diameter of the mandrel shall be stamped or engraved on some segment other than a runner. A suitable carrying case shall be furnished.

For pipe larger than 36 inches (900 mm) in diameter, deflection shall be determined by a method approved by the engineer. If a mandrel is selected, the minimum diameter, length, and other requirements shall conform to the above requirements.

Mandrel testing shall be conducted by the contractor in the presence of the engineer. Mandrel testing shall be at no direct pay.

(b) Metal Pipe: If the inside diameter of metal pipe or rise dimension of metal pipe arch deflects more than 5.0 percent from original dimensions, they shall be removed and reinstalled, unless they do not rebound or are damaged. Pipe or pipe arch which are damaged or do not rebound shall be removed and replaced at no direct pay. Measurement of deflection will be made by the engineer away from rerolled ends.

#### 701.10 CLEANING PIPES.

(a) Existing Pipes: Pipes designated to be cleaned shall be cleaned of soil, debris and other materials to the invert of the pipe. Designated pipes shall be cleaned by approved methods that will not damage the pipes. Any damage caused by the contractor's operations shall be satisfactorily repaired at no direct pay.

Removed soil, debris and other materials shall be disposed of in accordance with Subsection 202.02 or as otherwise approved in writing.

(b) Contractor Installed Pipes: Prior to final acceptance, pipes shall be cleaned of all debris and soil to the invert of the pipe at no direct pay.

## Supplemental Specifications (August 2008) Page 14 of 30

Removed soil, debris and other materials shall be disposed of in accordance with Subsection 202.02 or as otherwise approved in writing.

701.11 STUBBING AND PLUGGING PIPES. When it is required that pipes be plugged, such plugs shall be constructed of Class R concrete complying with Section 901. Thickness of plug and method of construction shall be as directed.

When new pipes are to be stubbed into new or existing pipes or other structures, the connection shall be made with approved mortar complying with Subsection 702.02.

- 701.12 MEASUREMENT. Pipe, both new and relaid, will be measured in linear feet (lin m) as follows unless stated otherwise.
- (a) Pipe not confined by fixed structures will be measured by the number of joints at the nominal length of each joint.
- (b) Pipe confined by fixed structures will be measured along the pipe between the termini of pipe in structure walls.
- (c) Pipe confined by a fixed structure on one end and unconfined at the other end will be measured along the pipe from the terminus of pipe in the structure wall to the unconfined end of pipe.
- (d) Fabricating of pipe tees, elbows and other fittings will be measured per each fitting. The length of pipe in such fittings will be included in the pay length measurement of pipes of which they form a part.
- (e) Excavation required for installation of pipes will not be measured for payment, except as otherwise specified in Subsection 203.14.
- (f) Furnishing and placing backfill material below existing ground level for pipes will not be measured for payment. Backfill material needed to complete backfill above natural ground and around pipes that extend above natural ground will be measured and payment will be made under applicable earthwork items. When specified, flowable fill will be measured and paid for in accordance with Section 710.
  - (g) Plugging and stubbing of pipes will not be measured for payment.
  - (h) Cleaning existing pipes will be measured by the length of pipe cleaned and accepted.
  - (i) Concrete collars will be measured per each.

#### 701.13 PAYMENT.

(a) Payment for pipe will be made at the contract unit price per linear foot (lin m) of the types and sizes specified.

When plastic pipe is specified on the plans or elected to be used by the contractor, payment will be made at the contract unit price per linear foot (lin m) of the types and sizes specified in accordance with the payment schedule of Table 701-1.

Table 701-1
Payment Schedule for Plastic Pipe

Percent Payment	Stage of Completeness		
75	After placement and backfill has been completed		
25	After the pipe has met vertical deflection requirements in accordance with Subsection 701.09(a)		

- (b) Payment for fabricating pipe tees, elbows and other fittings will be made at the contract unit price per each fitting.
- (c) When unstable conditions are encountered, the additional excavation will not be measured for payment; however, the additional materials furnished and placed for the pipe foundation will be measured and paid for as follows:
- (1) Granular Materials: Payment will be made under the embankment item. The net section volume of the materials will be multiplied by 3 to determine the pay volume. When the contract does not include a pay item for embankment, payment will be made in accordance with Subsection 104.02.
- (2) Bedding Material: Measurement and payment will be made in accordance with Section 726. When the contract does not include a pay item for bedding material, payment will be made in accordance with Subsection 104.02.
- (d) Payment for cleaning existing pipes will be made at the contract unit price per linear foot (lin m).
  - (e) Payment for concrete collars will be made at the contract unit price per each.

#### Payment will be made under:

Item No.	Pay Item	Pay Unit
701-01	Cross Drain Pipe (Size & Type)	Linear Foot (Lin m)
701-02	Cross Drain Pipe Arch (Size & Type)	Linear Foot (Lin m)
701-03	Storm Drain Pipe (Size & Type)	Linear Foot (Lin m)
701-04	Storm Drain Pipe Arch (Size & Type)	Linear Foot (Lin m)
701-05	Side Drain Pipe (Size)	Linear Foot (Lin m)
701-06	Side Drain Pipe Arch (Size)	Linear Foot (Lin m)
701-07	Yard Drain Pipe (Size)	Linear Foot (Lin m)
701-08	Relaying Pipe	Linear Foot (Lin m)
701-09	Fabricating Pipe Fittings	Each
701-10	Reinforced Concrete Pipe (Extension)	Linear Foot (Lin m)
701-11	Reinforced Concrete Pipe Arch (Extension)	Linear Foot (Lin m)
701-12	Corrugated Metal Pipe (Extension)	Linear Foot (Lin m)

Concrete may be placed by slip-form methods. Slip-formed concrete shall be placed with an approved machine designed to spread, vibrate, consolidate and finish concrete in one pass of the machine in such manner that minimum hand finishing is necessary. Sliding forms shall be

### Supplemental Specifications (August 2008) Page 17 of 30

rigidly held together to prevent spreading of forms. After the passing of the side forms there shall be no noticeable slumping of concrete.

- (c) Subgrade: The subgrade shall be thoroughly moistened immediately prior to placing concrete.
- (d) Placing and Finishing: Concrete shall be placed on the subgrade, struck off to required thickness and tamped sufficiently to bring the mortar to the surface. The surface shall be finished with a wood float or steel trowel followed by brushing to a slightly rough finish. Joints and edges shall be rounded with an edging tool having a 1/4-inch (6 mm) radius.
  - (e) Joints:
- (1) Expansion Joints: Expansion joints shall be filled with 1/2 inch (13 mm) thick preformed expansion joint filler. Expansion joints shall be installed at maximum 100-foot (30 m) intervals, and between intersecting paving and any fixed structure such as a building, bridge or curbing, and between intersecting paving and the handicapped curb ramps. Expansion joint material shall extend for the full width and depth of paving.
- (2) Weakened Plane: Weakened planes shall be formed by a jointing tool or other acceptable means. Weakened planes shall extend into concrete for at least 1/4 of the depth and shall be approximately 1/8 inch (3 mm) wide.
- a. Walks: Spacing of weakened planes for walks shall be equal to the width of walk.
- b. Drives: A longitudinal weakened plane shall be formed along the centerline of drives more than 16 feet (5 m) wide, and transverse weakened planes shall be formed at not more than 16-foot (5 m) intervals.
- c. Incidental Paving: Weakened planes for incidental paving shall be formed at intervals not exceeding 30 times the thickness of the concrete in length or width. Incidental paving poured adjacent to jointed concrete shall be jointed to match existing joints, with intermediate joints formed as necessary not to exceed the maximum joint spacing.
- (3) Construction Joints: Construction joints shall be formed around manholes, utility poles, etc., extending into paving and 1/4 inch (6 mm) thick preformed expansion joint filler shall be installed in these joints.
- (4) Tie-ins: Tie-ins of existing concrete shall be made by full depth sawing at no direct pay.
  - (f) Curing: Concrete shall be cured in accordance with Subsection 601.10.
- (g) Detectable Warning Surface for Handicap Ramps and At-Grade Sidewalk Intersections: Sidewalks, when intersecting with roadways, shall be equipped with a detectable warning surface system consisting of raised truncated domes as a transition between the sidewalk and the street as required by the Americans with Disabilities Act, 28 CFR Part 36, ADA Standards for Accessible Design.

Detectable warnings (truncated domes) shall be installed on the ramp surface over the full width of the ramp throat for a distance of 24 inches (600 mm) in the direction of travel from the back of the curb. Detectable warnings (truncated domes) shall also be installed on at-grade

sidewalks intersecting with roadways for a distance of 36 inches (900 mm) in the direction of travel from the end of the sidewalk. Truncated domes shall be laid out on a square grid in order to allow enough space for wheelchairs to roll between the domes.

### Supplemental Specifications (August 2008)

#### Page 18 of 30

Light reflectance of the truncated domes and the underlying surface must meet the 70 percent contrast requirement of ADAAG.

706.04 MEASUREMENT. Quantities of concrete walks, drives and incidental paving slabs for payment will be the design quantities as specified on the plans and adjustments thereto. Design quantities will be adjusted if the engineer makes changes to adjust to field conditions, if design errors are proven or if design changes are made. Design areas are based on the horizontal dimensions shown on the plans. Excavation, backfill, reinforcing steel and joint materials will not be measured for payment.

Handicapped curb ramps, including the detectable surface warning system, will be measured per each.

Detectable surface warning systems for at-grade sidewalk intersection will not be measured for payment.

706.05 PAYMENT. Payment for concrete walks, drives and incidental paving will be made on a lot basis at the contract unit price per square yard (sq m), adjusted in accordance with the following provisions. Payment for each lot will be made in accordance with Table 901-6. Size, sampling, and testing of each concrete lot shall be in accordance with the Materials Sampling Manual.

Payment for handicapped curb ramps, including the detectable surface warning system, will be made by each and shall include, but not limited to, curb transitions, detectable warning system, gutter, landing and base.

Payment will be made under:

Item No.	Pay Item	Pay Unit
706-01	Concrete Walk (inch (mm) Thick)	Square Yard (Sq m)
706-02	Concrete Drive ( inch (mm) Thick)	Square Yard (Sq m)
706-03	Incidental Concrete Paving	
	( inch (mm) Thick	Square Yard (Sq m)
706-04	Handicapped Curb Ramps	Each

#### SECTION 713 – TEMPORARY TRAFFIC CONTROL:

Subsection 713.06 - Payement Markings (08/06), Pages 400 - 403.

Delete Table 713-1, Temporary Pavement Markings and substitute the following.

Table 713-1
Temporary Pavement Markings<sup>1,2</sup>

		Temporary raven	10110 111111111111111111111111111111111	
		Two-lane Highways	Undivided Multilane Highways	Divided Multilane Highways
S H O R T E R M	ADT<1500; or ADT>1500 and time<3 days			
	ADT>1500; Time>3 days and<2 weeks	, .		
	All ADT's with time <2 weeks		Lane lines 4-foot (1.2m) tape on 40-foot (12 m) centers; double yellow centerline	
L O N G	All ADT's with time >2 weeks	Standard lane lines, no- passing zone markings, legends and symbols and when pavement width is 22 feet (6.7 m) or	centerlines, edge lines, and legends and	Standard lane lines, centerlines, edge lines, and legends and
T E R M		greater, edge lines		symbols.

<sup>&</sup>lt;sup>1</sup>No-passing zones shall be delineated as indicated whenever a project is open to traffic. <sup>2</sup>On all Asphaltic Surface Treatments that are open to traffic and used as a final wearing course or as an interlayer, temporary pavement markings (tabs) on 20-foot (6 m) centers shall be used, in lieu of the 4-foot (1.2 m) tape, on 40-foot (12 m) centers.

#### **SECTION 729 – TRAFFIC SIGNS AND DEVICES:**

<u>Subsection 729.02 – Materials (04/08), Pages 456 and 457.</u>

Delete the contents of Heading (a), Sign and Marker Sheeting, and substitute the following.

(a) Sign and Marker Sheeting: Sheeting material for sign panels, delineators, barricades and other markers shall comply with Section 1015. All permanent signs shall meet the requirements of ASTM D 4956, Type X.

# Supplemental Specifications (August 2008) Page 20 of 30

#### Subsection 729.04, Fabrication of Sign Panels and Markers (04/08), Pages 458 – 460.

Delete the third paragraph of Heading (c), Sheeting Application and substitute the following.

ASTM D 4956 Type X reflective sheeting shall be applied with an orientation determined by the engineer to obtain the optimum entrance angle performance. Fabricated vertical splices in ASTM D 4956 Type X reflective sheeting will be allowed only when the horizontal dimension of the sign face or attached shield is in excess of the maximum manufactured width of the sheeting. Fabricated vertical splices in ASTM D 4956 Type X reflective sheeting will also be allowed when the specified orientation will create excessive sheeting waste.

#### **SECTION 804 – DRIVEN PILES:**

Subsection 804.08 - Construction Requirements (04/07), Pages548 - 554.

Delete the first sentence of Heading (a), Preboring and substitute the following.

Preboring by augering, wet-rotary drilling, or other methods used to facilitate pile driving will not be permitted unless specified in the plans or allowed by the engineer.

Delete the first sentence of Heading (b), Jetting and substitute the following. Jetting will not be permitted unless allowed in the plans or allowed by the engineer.

#### **SECTION 901 – PORTLAND CEMENT CONCRETE:**

Subsection 901.06 – Quality Control of Concrete (08/06), Pages 726 – 731.

Add the following to the contents of Heading (b), Quality Control Tests.

The contractor shall be responsible for monitoring the components (cement, mineral and chemical admixtures, aggregates) in their mix to protect against any changes due to component variations. As component shipments arrive, the contractor shall verify slump, air content and set time by testing at ambient temperatures. The contractor shall make adjustments to the mix design to rectify any changes which would adversely affect constructability, concrete placement or the specifications. The contractor shall submit test results to the Department for review each day of paving. Testing to validate component consistency will be documented on the control logs. Conformance or variation in mix parameters (workability, set times, air content, etc.) shall be noted on the control logs. The contractor shall provide a copy of the proposed testing plan to the engineer for record. Acceptance of the plan does not relieve the contractor's responsibility for consistency.

#### Subsection 901.08 – Composition of Concrete (12/05), Pages 732 – 734.

Add the following to Heading (a).

The blended cement containing up to 50 percent of grade 100 or grade 120 ground granulated blast-furnace slag must be in compliance with Subsection 1001.04 for portland blast-furnace slag cement.

#### SECTION 1001 – HYDRAULIC CEMENT:

Subsection 1001.01 - Portland Cement (09/07). Page 749.

Delete the contents of this subsection and substitute the following.

1001.01 PORTLAND CEMENT. Portland cement shall be from an approved source listed in QPL 7 and shall comply with AASHTO M 85.

Alkali content calculated as sodium oxide equivalent shall not exceed 0.60 percent by weight for all types of cement.

#### **SECTION 1003 – AGGREGATES:**

Subsection 1003.02 – Aggregates for Portland Cement Concrete and Mortar (07/07), Pages 763 – 766.

Delete the contents of Heading (c), Aggregates for Types B and D Pavements, and substitute the following.

(c) Aggregates for Types B and D Pavements: For the combined aggregates for the proposed portland cement concrete pavement mix, the percent retained based on the dry weight (mass) of the total aggregates shall meet the requirements of Table 1003-1A for the type of pavement specified in the plans. Additionally, the sum of the percents retained on any two adjacent sieves so designated in the table shall be at least 12 percent of the total combined aggregates. The maximum amounts by weight (mass) of deleterious materials for the total aggregate shall be the same as shown in Subsection 1003.02(b).

# Supplemental Specifications (August 2008) Page 22 of 30

Table 1003-1A
Aggregates for Types B and D Pavements

U.S. Sieve	Metric Sieve	Percent Reta Combined	ined of Total Aggregates ent Type
		Type B	Type D
2 1/2 inch	63 mm	0	0
2 inch	50 mm	0	0-20
1 1/2 inch	37.5 mm	0-20	0-20
1 inch	25.0 mm	0-20	5-20
3/4 inch	19.0 mm	5-20	5-20
1/2 inch	12.5 mm	5-20	5-20
3/8 inch	9.5 mm	5-20	5-20
No. 4	4.75 mm	5-20	5-20
No. 8	2.36 mm	5-20	5-20
No. 16	1.18 mm	5-20	5-20
No. 30	600 μm	5-20	5-20
No. 50	300 μm	0-20	0-20
No. 100	150 μm	0-20	0-20
No. 200	75 μm	0-5	0-5

Note: For the sieves in the shaded areas, the sum of any two adjacent sieves shall be a minimum of 12 percent of the total combined aggregates.

Each type of aggregate to be used in the proposed mixture shall be sampled and tested individually. The percent of total combined aggregates retained shall be determined mathematically based on the proportions of the combined aggregate blend. All gradation calculations shall be based on percent of dry weight (mass).

#### SECTION 1005 – JOINT MATERIALS FOR PAVEMENTS AND STRUCTURES:

Subsection 1005.04 – Combination Joint Former/Sealer (11/05), Pages 782 and 783.

Delete Heading (a) and substitute the following.

(a) Description: This joint former/sealer is intended for use in simultaneously forming and sealing a weakened plane in portland cement concrete pavements.

The material shall consist of an elastomeric strip permanently bonded either mechanically or chemically at the top of each of two rigid plastic side frames and covered with a removable plastic top cap. Side frames shall be of such configuration that when the sealer is inserted into plastic concrete and vibrated, a permanent bond forms between side frames and concrete.

Delete Heading (b)(1) and substitute the following.

(1) Elastomer: The elastomer strip portion of the material shall be manufactured from vulcanized elastomeric compound using polymerized chloroprene or thermoplastic vulcanizate as the base polymer, and shall comply with the following requirements:

<u>Property</u>	ASTM Test Method	Require	<u>ements</u>
		Polymerized Chloroprene	Thermoplastic Vulcanizate
Tensile Strength, kPa, Min. Elongation at Break, % Min. Hardness, Shore A Properties after Aging, 70 h @ 100°C Tensile Strength, % Loss, Max. Elongation, % loss, Max. Hardness, pts. increase, Max. Ozone Resistance, 20% strain or bentloop,	D 412 D 412 D 2240 D 573	12,400 200 65 ± 10 20 25 10	7,400 400 65 ± 10 20 25 10
300 pphm in air, 70 h @ 40°C Oil Swell, IRM 903, 70 h @ 100°C, wt change, % Max.	D 1149 D 471	no cracks 45	no cracks 75

Delete Headings (b)(2) and (b)(3) and substitute the following:

- (2) Bond of Elastomer to Plastic: The force required to shear the elastomer from the plastic shall be a minimum of 5.0 pounds per linear inch (90 g/mm) of sealer when tested in accordance with DOTD TR 636.
- (3) Bond of Plastic to Cement Mortar: This bond will be evaluated and shall meet the following requirements:

The force required to separate the cement mortar from the plastic shall be a minimum of 5.0 pounds per linear inch (90 g/mm) of sealer when tested in accordance with DOTD TR 636.

#### SECTION 1006 - CONCRETE AND PLASTIC PIPE:

Subsection 1006.09 – Plastic Yard Drain Pipe (06/07), Page 789.

Delete the contents of Subheading (a)(3), Ribbed Polyvinyl Chloride Pipe (RPVCP) and substitute the following.

Ribbed Polyvinyl Chloride Pipe (RPVCP): Ribbed Polyvinyl Chloride Pipe shall comply with ASTM F 794, Series 46 or ASTM F 949 (46 psi).

#### **SECTION 1013 – METALS:**

Subsection 1013.09 - Steel Piles (08/06) Page 822.

Delete the title and references to "Steel Piles" in this subsection and substitute "Steel H Piles".

#### **SECTION 1015 – SIGNS AND PAVEMENT MARKINGS:**

Subsection 1015.04 – Sign Panels (05/07), Pages 832 and 833.

Delete the contents of Heading (a), Permanent Sign Panels and substitute the following.

## Supplemental Specifications (August 2008) Page 24 of 30

(a) Permanent Sign Panels: Flat panels shall be aluminum sheets or plates complying with ASTM B 209, Alloy 6061-T6 or Alloy 5052-H38. Extruded aluminum panels shall comply with ASTM B 221 (ASTM B 221M), Alloy 6063-T6 and after fabrication, have a flatness equal to or less than 0.031 inch per foot of length and 0.004 inch per inch of width.

#### Subsection 1015.05 - Reflective Sheeting (04/08), Pages 833 – 838.

Delete the contents of this subsection and substitute the following. 1015.05 REFLECTIVE SHEETING.

- (a) Permanent and Temporary Standard Sheeting: Reflective sheeting shall be one of the following standard types as specified on the plans and complying with ASTM D 4956 except as modified herein. Permanent warning, regulatory, guide and supplemental guide sign sheeting shall meet the requirements of ASTM D 4956 Type X. Reflective sheeting for temporary signs and devices shall meet the requirements of ASTM D 4956 Type III except as noted in Subsection 1015.05(f). Reflective sheeting shall be an approved product listed in QPL 13.
- Type III A high-intensity retroreflective sheeting that is typically encapsulated glass-bead retroreflective material.
- Type VI An elastomeric high-intensity retroreflective sheeting without adhesive. This sheeting is typically a vinyl microprismatic retroreflective material.
- Type X A super high-intensity retroreflective sheeting having highest retroreflectivity characteristics at medium distances. This sheeting is typically an unmetalized microprismatic retroreflective element material.
- (b) Fluorescent Pink Retroreflective Sheeting: Signs for temporary control of traffic through incident management areas shall be Type VI fluorescent pink retroreflective sheeting and shall comply with the MUTCD. Temporary traffic control signs for incident management shall be placed to notify motorists of upcoming incidents on the roadway, and shall be removed from public view once the incident has been managed. Physical properties shall comply with ASTM D 4956. Photometric properties shall be as follows.
- (1) Retroreflectivity: Minimum Coefficients of Retroreflection shall be as specified in Table 1015-1.

Table 1015-1
Coefficients of Retroreflection for Fluorescent Pink Sheeting<sup>1</sup>

Observation Angle, degrees	Entrance Angle, degrees	Fluorescent Pink
0.2	-4	100
0.2	+30	40
0.5	-4	40
0.5	+30	15

Minimum Coefficient of Retroreflection (R<sub>A</sub>) (cd lx<sup>-1</sup>m<sup>-2</sup>)

(2) Color and Daytime Luminance: Color Chromaticity Coordinates and Daytime Luminance Factors shall be as specified in Table 1015-2.

Table 1015-2
Fluorescent Pink Color Specifications Limits (Daytime)

				nates (cor			zuj tililoj	Luminance
			<i>y</i>	14105 (001	nei point			Factor, min.
	1		2		3		4	Y%
х	у	. X	у	X	у	X	_ y	25
0.450	0.270	0.590	0.350	0.644	0.290	0.536	0.230	23

<sup>1</sup>The four pairs of chromaticity coordinates measured with CIE 2° Standard Observer and 45/0 (0/45) geometry and CIE D65 Standard Illuminant.

- (c) Adhesive Classes: The adhesive required for retroreflective sheeting shall be Class 1 (pressure sensitive) as specified in ASTM D 4956.
- (d) Accelerated Weathering: Reflective sheeting, when processed, applied and cleaned in accordance with the manufacturer's recommendations shall perform in accordance with the accelerated weathering standards in Table 1015-3.

#### Supplemental Specifications (August 2008) Page 26 of 30

Table 1015-3 Accelerated Weathering Standards<sup>1</sup>

			OTELEGE TO CALL	<del></del>		
		Retrore	eflectivity <sup>2</sup>		Col	lorfastness <sup>3</sup>
Туре	Oran Fluore Ora	escent	All colors, orange/Fluc Orang	prescent	Orange/ Fluorescent Orange	All colors, except orange/Fluorescent Orange
III	1 year	804	3 years	80 <sup>4</sup>	1 year	3 years
III (for drums)	1 year	80 <sup>4</sup>	1 year	80 <sup>4</sup>	1 year	l year
VI	1/2 year	50 <sup>5</sup>	1/2 year	50 <sup>5</sup>	1/2 year	1/2 year
X	1 year	80 <sup>6</sup>	3 years	80 <sup>6</sup>	1 year	3 years

<sup>&</sup>lt;sup>1</sup>At an angle of 45° from the horizontal and facing south in accordance with ASTM G 7 at an approved test facility in Louisiana or South Florida.

(e) Expected Sign Life Data and Performance: The sheeting manufacturer shall supply expected retroreflectivity service life curves for each of the following sign sheeting colors: white, green, blue, brown, red, and yellow. The service life curves shall be plots of the 95 percent expected life plotted on an x-y graph with life years on the x-axis and retroreflectivity on the y-axis. The expected life shall account for worst case installations, equivalent to an installation in South Louisiana with the sign facing to the South. The sheeting manufacturer shall also supply a table of expected life values taken from the service life curves for Revision Number 2 to the 2003 Edition of the MUTCD minimum reflectivity requirements published in the Federal Register on December 21, 2007. Reflective sheeting for signs, when processed, applied and cleaned in accordance with the manufacturer's recommendations shall perform outdoors in accordance with the performance standards in Table 1015-4.

<sup>&</sup>lt;sup>2</sup>Percent retained retroreflectivity of referenced table after the outdoor test exposure time specified.

<sup>&</sup>lt;sup>3</sup>Colors shall conform to the color specification limits of ASTM D 4956 after the outdoor test exposure time specified.

<sup>&</sup>lt;sup>4</sup>ASTM D 4956, Table 8.

<sup>&</sup>lt;sup>5</sup>ASTM D 4956, Table 13.

<sup>&</sup>lt;sup>6</sup>ASTM D 4956, Table 4.

Table 1015-4
Reflective Sheeting Performance Standards

<u> </u>	Ret	roreflectivi	ty <sup>1</sup> Durabilit	ty <sup>2</sup>	
Туре	Orar Fluore Orar	escent	All colors, orange/Flue Oran	orescent	Colorfastness <sup>3</sup>
III	3 years	80 <sup>4</sup>	10 years	80 <sup>4</sup>	3 years
X	3 years	80 <sup>5</sup>	7years	80 <sup>5</sup>	3 years

<sup>&</sup>lt;sup>1</sup>Percent retained retroreflectivity of referenced table after installation and the field exposure time specified.

(f) Temporary Signs, Barricades, Channelizing Devices, Drums and Cones: Reflective sheeting for temporary signs, barricades and channelizing devices, shall meet the requirements of ASTM D 4956, Type III except that temporary warning construction signs used on the mainline of freeways and expressways shall be fluorescent orange and meet the requirements of ASTM D 4956, Type X.

Reflective sheeting for vertical panels shall meet the requirements of ASTM D 4956, Type III.

Reflective sheeting for drums shall be a minimum of 6 inches (150 mm) wide and shall meet the requirements of ASTM D 4956, Type III, and the Supplementary Requirement S2 for Reboundable Sheeting as specified in ASTM D 4956. Reflective sheeting for traffic cone collars shall meet the requirements of ASTM D 4956, Type III or Type VI.

(g) Sheeting Guaranty. The contractor shall provide the Department with a guaranty from the sheeting manufacturer stating that if the retroreflective sheeting fails to comply with the performance requirements of this subsection, the sheeting manufacturer shall do the following:

<sup>&</sup>lt;sup>2</sup>All sheeting shall maintain its structural integrity, adhesion and functionality after installation and the field exposure time specified.

<sup>&</sup>lt;sup>3</sup>All colors shall conform to the color specification limits of ASTM D 4956 after installation and the field exposure time specified.

<sup>&</sup>lt;sup>4</sup>ASTM D4956, Table 8.

<sup>&</sup>lt;sup>5</sup>ASTM D 4956, Table 4.

#### Supplemental Specifications (August 2008) Page 28 of 30

Table 1015-5
Manufacturer's Guaranty-Reflective Sheeting

		arci s Gaaranty Reflec	
Туре	its field location effectiveness at no c	to its original ost to the Department	Manufacturer shall replace the sheeting required to restore the sign face to its original effectiveness at no cost to the Department if failure occurs during the time period <sup>1</sup> as specified below
	Orange/Fluorescent Orange	All colors, except orange/Fluorescent Orange	All colors, except orange/Fluorescent Orange
III	<3 years	<7 years	7-10 years
X	<3 years	<5 years	5-7 years

<sup>&</sup>lt;sup>1</sup> From the date of sign installation.

Replacement sheeting for sign faces, material, and labor shall carry the unexpired guaranty of the sheeting for which it replaces.

The sign fabricator shall be responsible for dating all signs with the month and year of fabrication at the time of sign fabrication. This date shall constitute the start of the guaranty obligation period.

#### Subsection 1015.11 - Preformed Plastic Pavement Marking Tape (06/07), Pages 842 - 844.

Delete the contents of this subsection and substitute the following.

#### 1015.11 PREFORMED PLASTIC PAVEMENT MARKING TAPE.

- (a) General: Preformed plastic pavement marking tape shall be approved products listed on QPL 64 and shall comply with ASTM D4505 Retroreflectivity Level I or Level II, or DOTD Intersection Grade (as specified below), except as modified herein. The marking tape shall be Class 2 or 3. The type and color shall be in accordance with the plans and the MUTCD.
- (b) Thickness: All preformed plastic pavement marking tape shall have a minimum overall thickness of 0.060 inches (1.5 mm) when tested without the adhesive.
- (c) Friction Resistance: The surface of the Retroreflectivity Level II preformed plastic pavement marking tape shall provide a minimum frictional resistance value of 35 British Polish Number (BPN) when tested according to ASTM E303. The surface of the Retroreflectivity Level I and DOTD Intersection Grade preformed plastic pavement marking tape shall provide a minimum frictional resistance value of 45 BPN when tested according to ASTM E303. Values for the Retroreflectivity Level I material with a raised surface pattern as defined in ASTM D4505 are calculated by averaging values taken at downweb and at a 45 degrees angle from downweb.

(d) Retroreflective Requirements: The preformed plastic pavement marking tape shall have the minimum initial specific luminance values shown in Table 1015-7 when measured in accordance with ASTM D 4061.

Table 1015-7
Specific Luminance of Preformed Plastic Tape

	Observation	Entrance	Specific L (mcd/s	
Туре	Angle, degrees	Angle, degrees	White	Yellow
Retroreflectivity Level I	1.05	88.76	500	300
DOTD Intersection Grade	1.05	88.76	375	250
Retroreflectivity Level II	1.05	88.76	250	175

(e) Durability Requirements: The DOTD Intersection Grade preformed plastic pavement marking tape shall show no appreciable fading, lifting or shrinkage for a least 12 months after placement when placed in accordance with the manufacturer's recommended procedures on pavement surfaces having a daily traffic count not to exceed 15,000 ADT per lane.

The Retroreflectivity Level I preformed plastic pavement marking tape shall show no appreciable fading, lifting or shrinkage for a least 4 years after placement for longitudinal lines and at least 2 years after placement for symbols and legends.

The Retroreflectivity Level I preformed plastic pavement marking tape shall also retain the following reflectance values for the time period detailed in Table 1015-8.

Table 1015-8
Retained Specific Luminance for Retroreflectivity Level I
Preformed Plastic Pavement Marking Tape

1101	STITLE OF THE SHEET OF THE STATE	<u></u>	<del>-</del>	
			Specific 1	Luminance
	Observation	Entrance	(mcd/s	sq m/lx)
<u>Time</u>	Angle, degrees	Angle, degrees	White	Yellow
1 year	1.05	88.76	400	240
4 years (2 years for symbols and legend)	1.05	88.76	100	100

(f) Plastic Pavement Marking Tape Guaranty (DOTD Intersection Grade and Retroreflectivity Level I): If the plastic pavement marking tape fails to comply with the performance and durability requirements of this subsection within 12 months for DOTD Intersection Grade and 4 years for Retroreflectivity Level I, the manufacturer shall replace the plastic pavement marking material at no cost to the Department.

#### SECTION 1020 – TRAFFIC SIGNALS:

Subsection 1020.01 - Traffic Signal Heads (06/07), Pages 873 - 884.

Delete the contents of Heading (a), General Requirements and substitute the following.

# Supplemental Specifications (August 2008) Page 30 of 30

(a) General Requirements: Traffic signal sections, beacon sections and pedestrian signal sections shall be of the adjustable type. Materials and construction of each section shall be the same.

Signals shall be constructed for either 8 or 12-inch (200 mm or 300 mm) lens in accordance with the plans. Signal sections shall have three to five sections per face and beacon sections have only one section per face. Signal sections and associated brackets shall be finished inside and out with two coats of high grade dark olive green enamel, color number 14056 according to Federal Standard No. 595b with each coat independently baked. Visors shall be coated green on the outside and black on the inside. Edges shall be deburred and smooth with no sharp edges.

#### Subsection 1020.04 – Poles for Traffic Signal Systems (06/07), Pages 890 – 894.


Delete the sixth paragraph of Heading (a), Pedestal Support Signal Poles, and substitute the following.

Pedestals shall be finished with at least one coat of rustproofing primer, applied to a clean surface and one coat of dark olive green enamel, color number 14056 according to Federal Standard No. 595b.

DELANS TO BE   DEPARTMENT OF TRANSPORTATION & DEPARTMENT OF	TOTAL SHEETS	SHEETS = 14	TAX TABLES A DAY DAY TOP	STATE PROJECT PARISH NO.
PLANS OF PROPERTY  1-0.10  1-1-92  1-1	STANDAR	an PLANS TO BE	OF TRANSPORTATION &	256-06-0012
STATE HIGHWAY  10 1-0-08  STATE PROJECT NO. 256 06-0012  1-21-98  LA 44  STATE PROJECT NO. 256 06-0012  LA 44  STATION 10-00.000  END S. P. 256-06-0012  END S. 256-06-0012  END S. P. 256-06-0012  E	USED OF	IN THIS PROJECT	GEODOS OF PROPOSED	
1-21-96	STD. PLA EC-OI			
STATION 10-00.000  STATION 10-00.000  END S. P. 236-06-0012  STATION 10-00.000  END S. P. 236-06-0012  SOS STATION 10-00.000  END S. P. 236-06-0012  END S. P. 236-06-0012  SOS STATION 10-00.000  END S. P. 236-06-0012  END S. P. 2	MB-0 PM-0		STATE PROJECT NO. 256-06-0012 LA 942 - ST. JAMES PARISH ASCENSION PARISH LA 44	z
STATION   10-00.000				•
C.S.L.M. 1.800  STATION 105-04-00  END S. P. 256-06-0012  2009 A.D.T. 7.300  2019 A.D.T. 9,100  D. 55%  R. 10%  T. 13%  T. 13%  OF CONSTRUCTION: PATCHING AND OVERLAY  OF CONSTRUCTION: PATCHING AND OVERLAY  DEFINED  TO DESCRIPTION OF THE PROPERTY OF TOWARD OF THE PROPERTY OF TOWARD OF T		C.S.L.M. 0.000 STATION 10+00.00 BEGIN S. P. 256-06-0012	Burnside	
ST. JAMES 2009 A.D.T. • 7.300 2019 A.D.T. • 8.100 2019 A.D.T. • 7.300 2019 A.D.T. • 7.		C.S.L.M. 1.800 STATION +05+04.00 END S. P. 256-06-00 2		
OF CONSTRUCTION: PATCHING AND OVERLAY  APPROVED  THE COMMENDED FOR APPROVED  THE DESIGNAL DELIVERY  THE DESIGNAL D		TRAFFIC DATA S.P. 256-06-0012 2009 A.D.T. • 7,300 2019 A.D.T. • 8,100 D• 55% K* 10% T• 13%	Aben (1)	
APPROVED ATTE DECISION		CONSTRUCTION: PATCHING	AND OVERLAY	1
DEVICED DEVICED DATE OF ADDROVED				PRODICIN DELIVERY
	DATE	REVISION	DATE RECOMMENDED DATE	

	STATE PROJECT NO.	NO.	PARISH	SHEET NO.
	256-06-0012		ASCENSION	2
	TABLE OF CONTENTS			
SHEET NO.(S)	DESCRIPTION			
-	TITLE SHEET			
2	TABLE OF CONTENTS			
3	PROJECT NOTES		-	
4	TYPICAL SECTION			
5	TURNOUT AND PATCHING DETAILS			
9	SURFACING QUANTITIES			
7a - 7b	SUMMARY OF ESTIMATED QUANTITIES			
6-8	SUMMARY OF DRAINAGE STRUCTURES			
10-13	SIGNING SHEETS			
			=	

			170
	256-06-0012	ASCENSION	$\kappa$
HAY OR STRAW	BALES		
204-06-00100 TEMPORARY SILT FENCING			
THESE ITEMS TO BE LOCATED AS DIRECTED BY	DIRECTED BY THE PROJECT ENGINEER		
2)ITEM 729-16-00200 OBJECT MARKER ASSEMBLY (TYPE ITEM 729-16-00300 OBJECT MARKER ASSEMBLY (TYPE	YPE 2) YPE 3)		
THESE ITEMS TO BE USED TO REPLACE DAMAGED PROJECT ENGINEER	DAMAGED OR MISSING OBJECT MARKERS AS D	DIRECTED BY	
3)ITEM 509-01-00100 COLD PLANING ASPHALTIC PAVEMENT (1" AVERAGE ADJUST PAVEMENT PROFILE AT START AND END OF PROJECT, AND AT FOR LOCATIONS SEE SURFACING QUANTITIES.		DEPTH). THIS ITEM TO BE USED EACH BRIDGE STRUCTURE.	D 10
		PROJECT NOTES	
			_




- EXISTING SURFACING TO REMAIN. PRIOR TO PLACING REQUIRED ASPHALTIC CONCRETE WEARING COURSE, PREPARE PAVEMENT SURFACE PER SPECIAL PROVISIONS ITEM NS-500-00280.
- REQUIRED 2" SUPERPAVE ASPHALTIC CONCRETE WEARING COURSE LEVEL IF (V)
- (3) REQUIRED 3" AGGREGATE SURFACE COURSE SHOULDERS
- REQUIRED, ALL PAVEMENT MUTCD. BE IN ACCORDANCE WITH STANDARD PLAN PM-OI AND STRIPE ROADWAY SAME AS EXISTING. RAISED PAVEMENT MARKERS ARE MARKINGS SHALL 4

A MATCH EXISTING SLOPE

ROADWAY TYPICAL SECTION

LA 44

SECTION NOT TO SCALE SHEET 1 0F 1



STATION         DESCRIPTION         LENGTH         AVERAGE (1" Avg. Depth)           41+15.20         Paving Exception         3115.20         24         267           72+R8 RI         Roadway         3073.60         24         267	Aggregate Surface Course (3")  END AREA VOLUME  O.061 (YD³)  O.061 (66)  O.061 (66)  O.061 (66)  O.061 (66)  O.061 (66)  O.061 (66)  O.061 (66)	Superpave Asphaltic Concrete (2" Wearing Course) AREA (YD²) 266.7 266.7	
STATION         DESCRIPTION         LENGTH         AVERAGE           41+15.20         Paving Exception         3115.20         24           42+15.20         Roadway         100.00         24         267	(YD³)	(YD²)	
41+15.20         Paving Exception         3115.20         24            42+15.20         Roadway         100.00         24         267           72+R8 80         Roadway         3073.60         24         267	(YD³)	(YD²)	
41+15.20         Paving Exception         3115.20         24            42+15.20         Roadway         100.00         24         267           72+R8 Rn         Roadway         3073.60         24         267	1	1	
72+88 80 Roadway 100.00 24 267		4	
Roadway 3073.60 24		1	
12. CO:CO CO C			
72+88.00 73+88.00 Roadway 100.00 24 267 0.0	1		
87+40.47 Paying Exception 1351.67 24			
267			
88+40.47 104+04.00 Roadway 1563.53 24 0.0		4169.4	
100.00 24 267			
9504.00 1067	306	<del>-</del>	
SUPERPAVE ASPHALTIC CONCRETE  WEARING COURSE (2" THICK)  13432.5 YD² x (110 LB/YD²/IN ° 2IN) / 2000 LB / TON≈  5% ADDITIONAL FOR LEVELING≈	1477.6 TONS 73.9 TONS 1551.5 TONS		
SUPERPAVE AC, DRIVES, TURNOUTS, AND MISCELLANEOUS PAVED DRIVES & TURNOUTS			
	31.5 TONS		

O,
0
Ō
Ñ
<u>~</u>
2
4

**7**a

Page:

# Summary Of Estimated Quantities

Proposal ID: 256-06-0012 Federal Project Number:

9100

State Project Number: 256-06-0012

Proposal Description: LA 942 - ST. JAMES PARISH LINE

Item No.	Description	Supplemental Description	Alternate Set Member	Quantity	Units
		General Items			
202-02-32100	Removal of Pipe (Cross Drain)	30" bccmp		40.000	LNFT
204-06-00100	Temporary Stit Fencing			1,630.000	LNFT
401-02-00100	Aggregate Surface Course (Adjusted Vehicular Measurement)			306.000	сиур
502-01-00100	Superpave Asphaltic Concrete			1,551.500	NOT NOT
502-01-00200	Superpave Asphaltic Concrete, Drives, Turnouts and Miscellaneous			31.500	NOT
509-01-00100	Cold Planing Asphaltic Pavement			1,067.000	SQYD
510-01-00200	Pavement Patching (12" Minimum Thickness)			250.000	SQYD
701-02-01020	Cross Drain Pipe Arch (30" Equiv. RCPA)			40.000	LNFT
713-01-00100	Temporary Signs and Barricades			1.000	LUMP
713-03-01000	Temporary Pavement Markings (Broken Line) (4" Width) (4' Length)			0.954	MILE
713-03-02000	Temporary Pavement Markings (Broken Line) (4" Width) (10' Length)			0.420	MILE
713-04-01000	Temporary Pavement Markings (Solid Line) (4" Width)			3.316	MILE
713-06-00200	Temporary Reflectorized Raised Pavement Markers (Tabs)			127.000	EACH
				 	;   

# Notes:

**7**b

Page:

# Summary Of Estimated Quantities

Proposal ID: 256-06-0012 Federal Project Number:

poro

State Project Number: 256-06-0012

Proposal Description: LA 942 - ST. JAMES PARISH LINE


STATE PROJECT NO. PARISH SHEET NO.	256-06-0012 ASCENSION	SUMMARY OF DRAINAGE STRUCTURES	LA 44	SHEET I OF 2	S TANDARD PLAN OR PLAN OR SPECIAL DESCRIPTION (NOTES 1, 2) DETAIL		LIN. FEET LIN. FEET	L REQUIRED 30" EQUIV. RCPA SIDE DRAIN PIPE ARCH X 40"	L REMOVE EXISTING (1) 30" CROSS DRAIN X 40"		O OF OF OTHER
					S = 0			:	1	;	
								L			
					S T A T I	ΟZ		49+60.00	49+60.00		


NOTES:

<sup>1)</sup> Required joint types are shown in parenthesis at column headers. Example: Cross Drain Pipe Arch (Type 2 Joints)
2) Final catch basin, manhole, pipe locations, grate elevations, and inverts shall be as determined by the Contractor and approved by the Project Engineer.


		STATEP	STATE PROJECT	PARISH	SHEET NO.
		256-06-0012	3-0012	ASCENSION	ь
	SUMMARY OF DRAINAGE STRUCTURES				
	LA 44 SHEET 2 OF 2				
	MATERIAL TYPE ABBREVIATIONS	MINIMUM	SPACING FO	MINIMUM SPACING FOR MULTIPLE LINES OF PIPE OR	OF PIPE OR
BCCSP	BITUMINOUS COATED CORRUGATED STEEL PIPE		∢.	ARCH PIPE	
BCCSPA	BITUMINOUS COATED CORRUGATED STEEL PIPE ARCH	ROUND PIPES	PIPES	ARCH PIPES	IPES
CAP	CORRUGATED ALUMINUM PIPE			ROUND	
CAPA	CORRUGATED ALUMINUM PIPE ARCH	DIAMETER	SPACING	EQUIVALENT	SPACING
СВ	CATCH BASIN			SIZE	
CDP	CROSS DRAIN PIPE	18" thru 36"	1:-3"	18" thru 36"	1'-3"
CDPA	CROSS DRAIN PIPE ARCH	45"	1'-5"	45"	1'-5"
CMP	CORRUGATED METAL PIPE	48"	17"	48"	1.8.
CMPA	CORRUGATED METAL PIPE ARCH	54"	1'-9"	45	1'-10"
CPECP	CORRUGATED POLYETHYLENE CULVERT PIPE	.09	1-11"	.09	2'-0''
CSP	CORRUGATED GALVANIZED STEEL PIPE (NO COATING)	.99	2'-0"	99	2'-2"
CSPA	CORRUGATED GALVANIZED STEEL PIPE ARCH (NO COATING)	72"	2'-0"	72"	2'-3"
FBBCCSP	FIBER BONDED BITUMINOUS COATED CORRUGATED STEEL PIPE	78"	2'-6"	.82	2'-4"
FBBCCSPA	FIBER BONDED BITUMINOUS COATED CORRUGATED STEEL PIPE ARCH	84" & Larger	3'-0"	84"	2'-7"
MH	MANHOLE			.,06	2'-9"
PCCSP	POLYMER COATED CORRUGATED STEEL PIPE			.96	3,-0.
PCCSPA	POLYMER COATED CORRUGATED STEEL PIPE ARCH			102" & Larger	4,-0.,
PRCB	PRECAST REINFORCED CONCRETE BOX CULVERT				
PVCCP	POLYVINYL CHLORIDE CULVERT PIPE				
RCB	REINFORCED CONCRETE BOX CULVERT				
RCP	REINFORCED CONCRETE PIPE				
RCPA	REINFORCED CONCRETE PIPE ARCH				
RPECP	RIBBED POLYETHYLENE CULVERT PIPE				
RPVCCP	RIBBED POLYVINYL CHLORIDE CULVERT PIPE				
SD	SIDE DRAIN				
SDA	SIDE DRAIN ARCH				
SDP	STORM DRAIN PIPE				
SDPA	STORM DRAIN PIPE ARCH				

4	Z20-90-9SZ	DOS   NIA TO T   SOURCE   SO	4.41	TEMPORARY TRAFFIC CONTROL
3	PECENSION	COMMITTE COMMITTE AND A COMMITTE AND		TEMPORARY TRAFFILE CONTROL
	F. L. Schild, GATON PRIME STATES AND THE ADDRESS AND THE ADDRE	be subject by quicked or betriefle or the services with certainty and services with certainty and services with certainty from the services with the s	Liberting (see OPL)  Man used for exemple toowes, keptrey shell supplement of Amricoses that overlings toowed, keptrey shell supplement of Amricoses that overlined in extend lower into the streng excess to hyporogeneous. The Organ Birth Home overlines by supplementiations of the continually light may be used where obsequent owners is princed a consider.  One Type Birth into the prince special state is used to supplement the first laye for party that goes warring thous of the rest laye for the expert that goes warring thous of the center during may represent the first laye for the expert that goes warring thous of the center during my other first special on the center during my office of the center of the order of the center during the center of the order of the center of the order of the center of the c	
	That I ABLE. CHANGE ABLE MESSAGE. SUING.  When worken which the trooped were, including althoughes and duality lensa, checked because Signat (LAS) that he west on all interactive infermedable because Signat (LAS) that he west on all interactive infermedable because Signat (LAS) that he west on all interactive infermed and the ratio 2000 and should be detected with ratiosiffective TTC devices. CAS will be point for by such.  TTC devices, CAS will be pod for by such.  TTC devices of 2 miles in observe of the tiper for Interactives and 10 be determined by the Topiene on make highways.  If whiches one general paper five 2 mile (DAS, on additional CAS)  When the proposed on the signat for being the cool approximately of the size of the cool opportunistics.	CdS massions and be operious by the Darrich Trollic processors reported by the Darrich Trollic Processors reported to the processor reported by the Darrich Congestive between the processor or not instead to temperate it not removed. They should be shielded by particular to devices or not instable, they provide an observation of the processor of	F.L.AddRES  The Andresses must be anotherd. The contractor shall be responsible for training or observe that all begans for qualities to perform floogone duties. A Qualified Plagen is one that has convenient described to the convenient of the state private a standard tension (ATSSA). The Associated Senior of Describes Association (ATSSA). The Associated Senior of Confection of America (AGC) on the Confection of the Louisance DOTO'S WON'S Zone.  That Force. The Confection and the responsible for entire the Reger course approach.  The Man instance of tragger rate or minimum 15 rich extension places aspin on a minimum of included and associated was ARSI Costs 2 Line Sensions.	At the first personal and Akili Cleas 3 Lim Coun meaning from the floquer must be visible from the floquer odesire ventrions and the flower must be visible from the floquer odesire ventrion by.  The Stop Treffic Process  At barccose and use Typs 3 High intensity Sheeting in being a state of the arms Nichelly 350 residenment.  At Type III Bakelicanes  At Type III Bakelicanes  At Type III Bakelicanes  At Type III devices that he a minimum of 5 feet a langer must meat Nichelly 350 residenments.  AUTICO Website:  High://mustical.flawo.dol.agov/
	effic zentrale shoult sekeur its 2) detoke ond its MATCD. In one i ypteol dind may voory opening and in the Project Engleser. He perceives Engleser. Hes then one mile, they shoult a perioder to perceive beautie to be hose bean completed or where	Signs ever 10 at \$1 is about the mounted on two posts don't in a contract must be set 20 at \$1 had be mounted on the last tree post.  Signs ever 10 at \$1 is about the mounted on the posts tree post.  Signs and horse or minimum of two both set post.  Permonent input and theyev applicable or it centricis that be removed or both set of the se	CHANGELIZING DEVICES  Their Idebaving davices may be used: Their Idebaving davices may be used: Their Idebaving davices may be used: Druin ide streets developed one Super Center for/feterodered specing for the only develope developed to be used in itsure meas on the interesting system davig day-pile hours. Only druins seen be used in togens davig high operation.  The specing of throwshoped devices in a poster chould not assess to distinct the feet and to 1.0 thress the posted desect in man	to temporal should not the state that is possed sprine brill in the same of the state of the sta
		- 1. 1	eli the approved to the plore meet to be allered, the here appointed to the approved by the Project Engineer.  SPEED LINETS  Speed Linet and the housed by 10 mgh for my contrinction, mandenorte, or withy operation of contrinction, mandenorte, or withy operation of the register and or more of the followings of the contrinction ways as dependently. (5) and it is progressed of the original ways as dependently. (5) and it is not prepared to where it prevailed to the trees way required the clauses, from within trees way required the clauses, some within	boses  boses  re a prassar  that a consider England  rectains shall be related to the pract of the prace than the beat pant or the pract of





F-12



# STATE OF LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT



## CONSTRUCTION PROPOSAL RETURNABLES FOR

STATE PROJECT NO. 256-06-0012 LA 942 – ST. JAMES PARISH LINE ASCENSION PARISH ROUTE LA 44

#### **BID BOND**

	al bid amount as calculated by the Department in r than \$50,000. (See Section 102 of the Project
	, as Principal
(Bidder)	and , as Surety,
called the Department) in the sum of five percent (5	nt of Transportation and Development, (hereinafter 5%) of the bidder's total bid amount as calculated by I and Surety bind themselves, their heirs, executors,
Signed and sealed this day of	, 20
ST. JAMES PARISH LINE, located in ASCI accepted and the Principal, within the specified time	ENSION PARISH, ROUTE LA 44, if the bid is the, enters into the contract in writing and gives bond ent and performance of said contract, this obligation
Principal (Bidder or First Partner to Joint Venture)	If a Joint Venture, Second Partner
Ву	Ву
Authorized Officer-Owner-Partner	Authorized Officer-Owner-Partner
Typed or Printed Name	Typed or Printed Name
Su	rety
Ву	(Seal)
Agent or Att	omey-in-Fact
Typed or P	rinted Name
To receive a copy of the contract and subsequent correspect to the bid bonds, the following information n	rrespondence / communication from LA DOTD, with nust be provided:
Bonding Agency or Company Name	Address
Agent or Representative	Phone Number / Fax Number

07/07 Form CS-2A



#### Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page:

1

Contract ID: 256-06-0012

Project(s): 256-06-0012

SECTION: 1

General Items

Proposal Line	Item ID	Description	Approximate	Unit
Number		Unit Price (In Words, Ink or Typed)	Quantity	of Measure
0001	202-02-32100	Removal of Pipe (Cross Drain) 30" bccmp	40.000	LNFT
	-		· <del>-</del>	Dollars
	-			Cents
0002	204-06-00100	Temporary Silt Fencing	1,630.000	LNFT
	-			Dollars
	-			Cents
0003	401-02-00100	Aggregate Surface Course (Adjusted Vehicular Measurement)	306.000	CUYD
	-			Dollars
	-			Cents
0004	502-01-00100	Superpave Asphaltic Concrete	1,551.500	TON
	-			Dollars
		· ·		Cents
0005	502-01-00200	Superpave Asphaltic Concrete, Drives, Turnouts and Miscellaneous	31.500	TON
	-			Dollars
	-	**		Cents
0006	509-01-00100	Cold Planing Asphaltic Pavement	1,067.000	SQYD
	-			Dollars
	-		<del></del>	Cents
0007	510-01-00200	Pavement Patching (12" Minimum Thickness)	250.000	SQYD
	-			Dollars
	-			Cents
8000	701-02-01020	Cross Drain Pipe Arch (30" Equiv. RCPA)	40.000	LNFT
	-			Dollars
	-			Cents



### Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page:

2

SECTION: 1

General Items

Proposal Line	Item ID	Description	Approximate	Unit
Number		Unit Price (In Words, Ink or Typed)	Quantity	of Measure
0009	713-01-00100	Temporary Signs and Barricades		LUMP SUM
	-		-	Dollars
0010	713-03-01000	Temporary Pavement Markings (Broken Line) (4" Width) (4"	0.954	Cents MILE
5070	7 10 00 0 1000	Length)	0.354	MILE.
	-			Dollars
	-			Cents
0011	713-03-02000	Temporary Pavement Markings (Broken Line) (4" Width) (10' Length)	0.420	MILE
	-		<del></del>	Dollars
	-	787		Cents
0012	713-04-01000	Temporary Pavement Markings (Solid Line) (4" Width)	3.316	MILE
	-	- 110		Dollars Cents
0013	713-06-00200	Temporary Reflectorized Raised Pavement Markers (Tabs)	127.000	EACH
				Dollars
	-			Cents
0014	727-01-00100	Mobilization		LUMP SUM
	-			Dollars
	-			Cents
0015	729-16-00200	Object Marker Assembly (Type 2)	6.000	EACH
	-			Dollars Cents
0016	729-16-00300	Object Marker Assembly (Type 3)	4.000	EACH
	-			Dollars
	_			Cents



#### Louisiana Department of Transportation and Development

Proposal Schedule of Items

Page:

3

SECTION: 1

General Items

Proposal Line Number	Item ID	Description	Approximate Quantity	Unit of Measure
Number		Unit Price (In Words, Ink or Typed)	quantity	or measure
0017	731-02-00100	Reflectorized Raised Pavement Markers	127.000	EACH
	-		B4	Dollars
	-			Cents
0018	732-02-01000	Plastic Pavement Striping (Solid Line) (4" Width) (Thermoplastic 40 mil)	3.316	MILE
	-		11-1	Dollars
	-			Cents
0019	732-03-01000	Plastic Pavement Striping (Broken Line) (4" Width) (Thermoplastic 40 mil)	0.420	MILE
	-			Dollars
	-			Cents
0020	735-01-00100	Mailboxes	1.000	EACH
	-			Dollars
	_			Cents
0021	735-02-00100	Mailbox Supports (Single)	1.000	EACH
	-			Dollars
	_			Cents
0022	740-01-00100	Construction Layout		LUMP SUM
	_			Dollars
				Cents
0023	NS-500-00280	Surface Preparation		LUMP SUM
	_			Dollars
	_			Cents
0024	NS-500-00340	Saw Cutting Asphaltic Concrete Pavement	13,560.000	INLF
	_			Dollars
	_			Cents

1000
parp
ت جزيا م

4/8/2009

Proposal Schedule of Items Page:								
Contract ID: 256-06-0012	, , , <u>, , , , , , , , , , , , , , , , </u>	Project(s): 256-06-0012						
	Section: 1	Total:	·					
		Total Bid:						

CONSTRUCTION PROPOSAL SIGNATURE AND EXECUTION FORM
THIS FORM, THE SCHEDULE OF ITEMS, AND THE PROPOSAL GUARANTY MUST BE COMPLETED AS INDICATED AND SUBMITTED
TO THE LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT (DOTD) TO CONSTITUTE A VALID BID

TO THE ECCIONAGE PERARTMENT	THE TOTAL AND DEVELOPMENT (DOTD) TO CONSTITUTE A VALID BID
STATE PROJECT NO(S).	256-06-0012
FEDERAL AID PROJECT NO(S).	N/A
NAME OF PROJECT	LA 942 – ST. JAMES PARISH LINE
ANY AND ALL ADDENDA, AND THE SITE IN DOCUMENTS, THE MASTER COPY OF WHICH MATERIALS AND LABOR REQUIRED THEREIN AND LABOR REQUIRED THEREIN AND LABOR REQUIRED FOR SUCCESSFUL AN OF THE PRODUCTS OF THE UNIT PRICES BY MULTIPLIED BY THE ACTUAL QUANTITY OF AND FINAL PAYMENT FOR ALL WORK, LABONCEASE ONLY FOR PLAN CHANGES (CHANISS SUBMITTED IN ACCORDANCE WITH THE SPECIAL PROVISIONS, PLANS, SUPPLEMENTA AND BRIDGES (2006 EDITION). I (WE) UNDERS SCHEDULE OF ITEMS MULTIPLIED BY THE FOTHER FACTORS SPECIFIED TO BE APPLICABETHE COMPARISON OF BIDS. I (WE) UNDERSTRIFE COMPARISON OF BIDS. I TO BE FORFEITING OF MY (OUR) GOOD FAITH TO BE FORFEITING OF WEIGHT OF W	•
NONCOLLUSION DE	CLARATION (APPLICABLE TO FEDERAL-AID PROJECTS)
NOT DIRECTLY OR INDIRECTLY, ENTERED INTO A	INDER THE LAWS OF THE UNITED STATES AND THE STATE OF LOUISIANA THAT I (WE) HAVE ANY AGREEMENT, PARTICIPATED IN ANY COLLUSION, OR OTHERWISE TAKEN ANY ACTION IN DINNECTION WITH THE CONTRACT FOR THIS PROJECT NOR VIOLATED LA. R.S. 48:254.
BIDDER'S DBE GOA	L STATEMENT (APPLICABLE TO DBE GOAL PROJECTS)
WITH THE DBE PROVISIONS OF THIS CONTRACT, OR IF THE BIDDER CANNOT MEET THE REQUIRED	DVISION AS A DISADVANTAGED BUSINESS ENTERPRISE (DBE) GOAL PROJECT IN ACCORDANCE THE BIDDER ASSURES DOTD THAT HE/SHE WILL MEET OR EXCEED THE DBE CONTRACT GOAL. DBE GOAL, THE BIDDER ASSURES DOTD THAT HE/SHE HAS MADE AND CAN DOCUMENT GOOD GOAL REQUIREMENT IN ACCORDANCE WITH THE CONTRACT AND DBE PROGRAM MANUAL
ATTACHMENT(S) AND, IF NECESSARY, DOCUME WITHIN TEN BUSINESS DAYS AFTER THE OPENING	TE AND SUBMIT TO THE DOTD COMPLIANCE PROGRAMS OFFICE, FORM CS-6AAA AND NTATION OF GOOD FAITH EFFORTS MADE BY THE BIDDER TOWARD MEETING THE GOAL, G OF BIDS FOR THIS PROJECT, RESPONSIVENESS OF INFORMATION SUPPLIED IN THIS SECTION AND EXECUTION FORM IS GOVERNED BY THE DBE REQUIREMENTS INCLUDED WITHIN THE
	F LOUISIANA RESIDENTS TRANSPORTATION INFRASTRUCTURE MODEL PMENT (TIME) PROJECTS (APPLICABLE TO TIME PROJECTS)
(TIME) PROJECT AS DEFINED IN ACT NO. 16 OF TO	ROVISION AS A TRANSPORTATION INFRASTRUCTURE MODEL FOR ECONOMIC DEVELOPMENT HE 1989 FIRST EXTRAORDINARY SESSION OF THE LEGISLATURE WHICH ENACTED PART V OF UISIANA REVISED STATUTES OF 1950, COMPRISED OF R.S. 47:820,1 THROUGH 820.6.
ACCORDANCE WITH LOUISIANA R.S. 47:820.3.	NT OF THE EMPLOYEES EMPLOYED ON THIS TIME PROJECT WILL BE LOUISIANA RESIDENTS IN
NON PARTICIPATION IN PAYM	MENT ADJUSTMENT (ASPHALT CEMENT AND FUELS) STATEMENT
	VISION AS BEING SUBJECT TO PAYMENT ADJUSTMENT FOR ASPHALT CEMENT AND/OR FUELS, EXCLUSION FROM SAID PAYMENT ADJUSTMENT PROVISIONS THAT ARE ESTABLISHED BY
IF THE BIDDER DESIRES TO BE EXCLUDED FROM T	THESE PAYMENT ADJUSTMENT PROVISIONS,
THE BIDDER IS REQUIRED TO MARK HERE	
FAILURE TO MARK THIS BOX PRIOR TO BID OPENI	NG WILL CONSTITUTE FORFEITURE OF THE BIDDER'S OPTION TO REQUEST EXCLUSION.
	CS-14A

### BIDDER SIGNATURE REQUIREMENTS (APPLICABLE TO ALL PROJECTS)

THIS BID FOR THE CAPTIONED PROJECT IS SUBMITTED BY:

F	orm	Not	V	alid	for	Bid	Submittal
---	-----	-----	---	------	-----	-----	-----------

Name of Principal (Individual, Firm, Corporation, or Joint Venture)	If Joint Venture, Name of Second Partner
	11 Joint Venture, paine of Second Pattier
If Joint Venture, Name of First Partner	(Louisiana Contractor's License Number of Second Partner to Joint Venture)
(Louisiana Contractor's License Number of Bidder or First Partner to Joint Venture)	
	(Business Street Address)
(Business Street Address)	
	(Business Mailing Address, if different)
(Business Mailing Address, if different)	
	(Area Code and Telephone Number of Business)
(Area Code and Telephone Number of Business)	(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
,	(Telephone Number and Name of Contact Person)
(Telephone Number and Name of Contact Person)	•
	(Telecopier Number, if any)
(Telecopier Number, if any)	
CTING ON BEHALF OF THE BIDDER, THIS IS TO ATTEST THAT THE LEOVE CAPTIONED FIRM, CORPORATION OR BUSINESS, BY SUBMICCURACY OF ALL PROVISIONS OF THIS PROPOSAL, INCLUSIVE CERTIFICATIONS ABOVE AND IN THE SCHEDULE OF ITEMS AND FROM AND SUBMISSION OF THE SCHEDULE OF ITEMS AND PROPEGALLY BINDING OFFER BY THE BIDDER.	MISSION OF THIS BID, AGREES AND CERTIFIES THE TRUTH AND E OF THE REQUIREMENTS, STATEMENTS, DECLARATIONS AND PROPOSAL GUARANTY. EXECUTION AND SIGNATURE OF THIS
(Signature)	(Signature)
(Printed Name)	(Printed Name)
(Title)	(Title)
(Date of Signature)	(Date of Signature)
CONTRACTOR'S TOTAL BASE BID \$	
IT IS AGREED THAT THIS TOTAL, DETERMINED BY THE BIDDER, I PURPOSES OF OPENING AND READING BIDS ONLY, AND THAT TH PROJECT WILL BE DETERMINED FROM THE EXTENSION AND TOT	E LOW BID FOR THIS

CS-14AA 08/06