



BOBBY JINDAL
GOVERNOR

STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
P.O. Box 94245
Baton Rouge, Louisiana 70804-9245
www.dotd.la.gov
225-379-1485



WILLIAM D. ANKNER, Ph.D.
SECRETARY

June 2, 2009

STATE PROJECT NO. 742-36-0008
FEDERAL AID PROJECT NO. ARR-6033(009)
EARHART BOULEVARD (SEGMENT I) (HAMILTON ST. TO PINE ST.)
ORLEANS PARISH

SUBJECT: ADDENDUM NO. 2 (CONSTRUCTION PROPOSAL REVISION)
ELECTRONIC BIDDING AMENDMENT NO. 1

Gentlemen:

The following proposal revisions dated 06/02/2009 on the captioned project for which bids will be received on Wednesday, June 17, 2009 have been posted on <http://www.dotd.la.gov/cgi-bin/construction.asp>.

1. The Schedule of Items has been revised as follows: (24 pages)
 - a). Added Item 601-04, Portland Cement Concrete Pavement Coring.
 - b). Revised the quantity of Item S-150, Impact Attenuator.

Please note these revisions in the proposal and bid accordingly. Mandatory electronic bidding is required for this project, and electronic bids and electronic bid bonds must be submitted via www.bidx.com for this letting date.

Sincerely,

RANDAL D. SANDERS, P. E.
CONTRACTS & SPECIFICATIONS ENGINEER

Attachments

cc: Mr. Brian Buckel
Mr. Michael Stack
Mr. Francis Berger
Mr. Buddy Porta
Mr. Frederick Wetekamm
Mr. Eric Burges
Mr. Masood Rasoulia
City of New Orleans

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 4

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
601-04	45	EACH	PORTLAND CEMENT CONCRETE PAVEMENT CORING DOLLARS CENTS
602-05-I-03	320.0	SQUARE YARD	FULL DEPTH PATCHING OF JOINTED CONC PWMT (9" THICK) (48.1 SQ YDS & OVER) DOLLARS CENTS
701-03-F	4,770	LINEAR FOOT	STORM DRAIN PIPE (15" RCP) DOLLARS CENTS
701-03-G	1,181	LINEAR FOOT	STORM DRAIN PIPE (18" RCP) DOLLARS CENTS
701-03-I	1,150	LINEAR FOOT	STORM DRAIN PIPE (24" RCP) DOLLARS CENTS
701-03-K	844	LINEAR FOOT	STORM DRAIN PIPE (30" RCP) DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 5

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
701-03-M	333	LINEAR FOOT	STORM DRAIN PIPE (36" RCP) DOLLARS CENTS
701-09-A	26	EACH	FABRICATING PIPE FITTINGS (15"x15"x15") DOLLARS CENTS
701-09-B	6	EACH	FABRICATING PIPE FITTINGS (18"x18"x15") DOLLARS CENTS
701-09-C	5	EACH	FABRICATING PIPE FITTINGS (24"x24"x15") DOLLARS CENTS
701-09-D	3	EACH	FABRICATING PIPE FITTINGS (30"x30"x15") DOLLARS CENTS
701-09-E	1	EACH	FABRICATING PIPE FITTINGS (36"x36"x15") DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 6

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
701-09-F	5	EACH	FABRICATING PIPE FITTINGS (18"x18"x18") _____ DOLLARS _____ CENTS
702-02-G-01	54	EACH	MANHOLES (D-870) (STANDARD NO. 1) _____ DOLLARS _____ CENTS
702-02-G-02	6	EACH	MANHOLES (D-870) (STANDARD NO. 2) _____ DOLLARS _____ CENTS
702-02-G-03	2	EACH	MANHOLES (D-870) (STANDARD NO. 3) _____ DOLLARS _____ CENTS
702-02-H	1	EACH	MANHOLES (6178-B6) (SEWER MANHOLE) _____ DOLLARS _____ CENTS
702-02-I	7	EACH	MANHOLES (6179-F-2) (WATER VALVE MANHOLE) _____ DOLLARS _____ CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 7

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
702-03-H	1	EACH	CATCH BASINS (CB-05) DOLLARS CENTS
702-03-I	52	EACH	CATCH BASINS (D-873) (VERTICAL CATCH BASIN NO.1) DOLLARS CENTS
702-03-J	15	EACH	CATCH BASINS (D-873-A) (DOUBLE VERTICAL CATCH BASIN) DOLLARS CENTS
702-03-K	5	EACH	CATCH BASINS (D-3431-A) (SINGLE DRIVE-OVER CATCH BASIN) DOLLARS CENTS
702-03-L	9	EACH	CATCH BASINS (D-3264) (DROP INLET CATCH BASIN) DOLLARS CENTS
702-03-M	2	EACH	CATCH BASINS (D-3431-B) (DOUBLE DRIVE-OVER CATCH BASIN) DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 8

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
702-04-A	11	EACH	ADJUSTING MANHOLES DOLLARS CENTS
702-04-B	5	EACH	ADJUSTING CATCH BASINS DOLLARS CENTS
705-09	146	LINEAR FOOT	REBUILT FENCE DOLLARS CENTS
706-01-A	5,051.2	SQUARE YARD	CONCRETE WALK (4" THICK) DOLLARS CENTS
706-01-C	920.8	SQUARE YARD	CONCRETE WALK (6" THICK) DOLLARS CENTS
706-02-C	1,730.7	SQUARE YARD	CONCRETE DRIVE (6" THICK) DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 9

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
706-03-A	304.9	SQUARE YARD	INCIDENTAL CONCRETE PAVING (4" THICK) DOLLARS CENTS
707-01	13,505.5	LINEAR FOOT	CONCRETE CURB DOLLARS CENTS
707-03	961.4	LINEAR FOOT	COMBINATION CONCRETE CURB & GUTTER DOLLARS CENTS
713-01	LUMP	LUMP SUM	TEMPORARY SIGNS & BARRICADES DOLLARS CENTS
713-03-B	2.300	MILE	TEMPORARY PAVEMENT MARKINGS (BROKEN LINE) (4" WIDTH) (10' LENGTH) DOLLARS CENTS
713-04-A-01	3.100	MILE	TEMPORARY PAVEMENT MARKINGS (SOLID LINE) (4" WIDTH) (TYPE 1 REMOVABLE) DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 10

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
713-05-A	4	EACH	TEMPORARY PAVEMENT LEGENDS AND SYMBOLS (ARROW) DOLLARS CENTS
713-08	380	EACH	TEMPORARY PRECAST BARRIER (DOTD FURNISHED) DOLLARS CENTS
713-10	760	EACH	TEMPORARY PORTABLE BARRIER MOVEMENT DOLLARS CENTS
715-01	1,012	CUBIC YARD	TOPSOIL DOLLARS CENTS
717-01	60	POUND	SEEDING DOLLARS CENTS
718-01	2,000	POUND	FERTILIZER DOLLARS CENTS

N-10

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008 DATE: 06/02/09 08:45 PAGE: 11
OTHER PROJECTS: 742-36-0008

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
722-02	1	EACH	PROJECT SITE LABORATORY (EQUIPPED) DOLLARS CENTS
725-01	925.0	SQUARE YARD	TEMPORARY DETOUR ROADS DOLLARS CENTS
726-01	1,038.2	CUBIC YARD	BEDDING MATERIAL DOLLARS CENTS
727-01	LUMP	LUMP SUM	MOBILIZATION DOLLARS CENTS
729-01	260.0	SQUARE FOOT	SIGN (TYPE A) DOLLARS CENTS
731-02	424	EACH	REFLECTORIZED RAISED PAVEMENT MARKERS DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 12

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
732-01-B	6,490	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (6" WIDTH) _____ DOLLARS _____ CENTS
732-01-C	2,072	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (8" WIDTH) _____ DOLLARS _____ CENTS
732-01-E	897	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (24" WIDTH) _____ DOLLARS _____ CENTS
732-02-A	3.100 MILE		PLASTIC PAVEMENT STRIPING (SOLID LINE) (4" WIDTH) _____ DOLLARS _____ CENTS
732-03-A-01	2.300 MILE		PLASTIC PAVEMENT STRIPING (BROKEN LINE) (4" WIDTH) PREFORMED MARKING TAPE TYPE V _____ DOLLARS _____ CENTS
732-04-A	18 EACH		PLASTIC PAVEMENT LEGENDS & SYMBOLS (ARROW) _____ DOLLARS _____ CENTS

N-12

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 13

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
732-04-B	2	EACH	PLASTIC PAVEMENT LEGENDS & SYMBOLS (DOUBLE ARROW) DOLLARS CENTS
732-04-C	6	EACH	PLASTIC PAVEMENT LEGENDS & SYMBOLS (ONLY) DOLLARS CENTS
732-04-E	1	EACH	PLASTIC PAVEMENT LEGENDS & SYMBOLS (SCHOOL CROSSING) DOLLARS CENTS
732-05	1.100	MILE	REMOVAL OF EXISTING MARKINGS DOLLARS CENTS
740-01	LUMP	LUMP SUM	CONSTRUCTION LAYOUT DOLLARS CENTS
741-01-C	688	LINEAR FOOT	WATER MAIN (8" PVC) DOLLARS CENTS

N-13

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 14

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
741-02-C	5	EACH	GATE VALVE (8") DOLLARS CENTS
741-04	5	EACH	FIRE HYDRANT DOLLARS CENTS
741-09	20	EACH	ADJUSTING WATER HOUSE CONNECTIONS DOLLARS CENTS
742-02	20	EACH	ADJUSTING SANITARY SEWER HOUSE CONNECTIONS DOLLARS CENTS
812-01-B	82.96	MFEM	TREATED TIMBER (COASTAL TREATMENT) DOLLARS CENTS
S-001	38,910	SQUARE YARD	GEOGRID DOLLARS CENTS

N-14

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 15

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-002	10	EACH	TEMPORARY CONSTRUCTION ENTRANCE _____ DOLLARS _____ CENTS
S-102	10,840	LINEAR FOOT	SAW CUTTING (inch/foot) _____ DOLLARS _____ CENTS
S-103	160.0	SQUARE YARD	REINFORCED CONCRETE BUS PAD (9" THICK, 4000 PSI) (12'X 60') _____ DOLLARS _____ CENTS
S-104	36	EACH	RELOCATE LIGHT STANDARD _____ DOLLARS _____ CENTS
S-105	50.0	EACH	EXPLORATION AND LOCATION OF ALL EXISTING UTILITIES _____ DOLLARS _____ CENTS
S-106	3	EACH	REMOVE AND SALVAGE LIGHT STANDARDS _____ DOLLARS _____ CENTS

N-15

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 16

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-107	2,500	LINEAR FOOT	STREET LIGHT CABLE IN CONDUIT DOLLARS CENTS
S-108	10	EACH	EMERGENCY ELECTRICAL SPLICES DOLLARS CENTS
S-120	8	EACH	SIGNAL SUPPORT (PEDESTAL, MOUNTED) DOLLARS CENTS
S-121	2	EACH	SIGNAL SUPPORT (25' SINGLE MAST ARM) DOLLARS CENTS
S-122	2	EACH	SIGNAL SUPPORT (30' SINGLE MAST ARM) DOLLARS CENTS
S-123	8	EACH	SIGNAL SUPPORT (35' SINGLE MAST ARM) DOLLARS CENTS

N-16

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 17

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-124	3	EACH	SIGNAL SUPPORT (40' SINGLE MAST ARM) DOLLARS CENTS
S-125	4	EACH	SIGNAL SUPPORT (45' SINGLE MAST ARM) DOLLARS CENTS
S-126-A	41	EACH	SIGNAL HEAD - HORIZONTAL, (3-SECTION, R Y G), (12" LED LENS) DOLLARS CENTS
S-126-B	30	EACH	SIGNAL HEAD - VERTICAL, (3-SECTION R Y G), (12" LED LENS) DOLLARS CENTS
S-126-C	2	EACH	SIGNAL HEAD - VERTICAL, (3-SECTION R YLT GLT), (12" LED LENS) DOLLARS CENTS
S-126-D	3	EACH	SIGNAL HEAD - HORIZONTAL, (3-SECTION R YRT GRT), (12" LED LENS) DOLLARS CENTS

N-17

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 18

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-127	3	EACH	SIGNAL CONTROLLER - (NEMA TS-2, TYPE 6 BASE MOUNTED CABINET) DOLLARS CENTS
S-128	8,838	LINEAR FOOT	CONDUCTOR 7C (SINGLE, #14 AWG STRANDED) TRAFFIC SIGNAL CABLE DOLLARS CENTS
S-129	1,394	LINEAR FOOT	JACK OR BORED CONDUIT DOLLARS CENTS
S-130	3	EACH	SIGNAL SERVICE (PEDESTAL MOUNT) DOLLARS CENTS
S-131	37	LINEAR FOOT	CONDUIT 1" PVC IN EARTH DOLLARS CENTS
S-132	4,600	LINEAR FOOT	CONDUIT 2" PVC IN EARTH DOLLARS CENTS

N-18

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

DATE: 06/02/09 08:45 PAGE: 19

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-133	20	LINEAR FOOT	CONDUIT 3" PVC IN EARTH DOLLARS CENTS
S-134	724	LINEAR FOOT	CONDUIT 3" PVC JACK AND BORE DOLLARS CENTS
S-135	106	LINEAR FOOT	CONDUIT 4" PVC IN EARTH DOLLARS CENTS
S-136	50	LINEAR FOOT	CONDUIT 1" (RIGID) DOLLARS CENTS
S-137	23	EACH	UNDERGROUND JUNCTION BOX (TYPE D) DOLLARS CENTS
S-138	16	EACH	UNDERGROUND JUNCTION BOX (TYPE F) DOLLARS CENTS

N-19

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 20

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-139	3	EACH	TRAFFIC MANHOLE DOLLARS CENTS
S-140	628	LINEAR FOOT	LOOP DETECTORS (SAW LOOP SLOT IN PAVEMENT) DOLLARS CENTS
S-141	6,200	LINEAR FOOT	CABLE LOOP LEAD IN DOLLARS CENTS
S-142	5	EACH	OPTICAL EMITTER DOLLARS CENTS
S-143	1,184	LINEAR FOOT	CONDUCTOR, 3C (SIGNAL, #14 AWG STRANDED) OPTICAL DETECTOR CABLE DOLLARS CENTS
S-144	8	EACH	UNI-DIRECTIONAL OPTICAL DETECTORS DOLLARS CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 21

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-146	3,753	LINEAR FOOT	CONDUCTOR, 1-6PR INTERCONNECT CABLE DOLLARS CENTS
S-148	30	EACH	STREET NAME SIGNS (ON NEW POST) DOLLARS CENTS
S-149	7,276	LINEAR FOOT	CONDUCTOR, 2C/OS (LOOP LEAD-IN, #14 AWG STRANDED) LOOP WIRE DOLLARS CENTS
S-150	11	EACH	IMPACT ATTENUATOR DOLLARS CENTS
S-151	100	HOURL	POLICE TRAFFIC CONTROL DOLLARS CENTS
S-152	400	LINEAR FOOT	CONDUIT 2" PVC JACK AND BORE DOLLARS CENTS

N-21

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 22

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-153	316	LINEAR FOOT	CONDUIT 4" PVC JACK AND BORE _____ DOLLARS _____ CENTS
S-154	4,750	LINEAR FOOT	TRENCHING AND BACKFILLING _____ DOLLARS _____ CENTS
S-155	40	SQUARE FOOT	SIGNS (R3-1) _____ DOLLARS _____ CENTS
S-156	4	SQUARE FOOT	SIGNS (R3-2) _____ DOLLARS _____ CENTS
S-157	4	SQUARE FOOT	SIGNS (R3-5R) _____ DOLLARS _____ CENTS
S-158	6.3	SQUARE FOOT	SIGNS (R3-7R) _____ DOLLARS _____ CENTS

N-22

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 23

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-159	12.5	SQUARE FOOT	SIGNS (R5-1) DOLLARS CENTS
S-160	8	SQUARE FOOT	SIGNS (R10-10) DOLLARS CENTS
S-161	42	SQUARE FOOT	SIGNS (SPECIAL, YIELD TO PEDESTRIAN) DOLLARS CENTS
S-162	87.5	SQUARE FOOT	SIGNS (SPECIAL, STREET NAME) DOLLARS CENTS
S-163	31	LINEAR FOOT	CONDUCTOR, 3C (POWER, #6 AWG) DOLLARS CENTS
S-201	LUMP	LUMP SUM	SEWERAGE AND WATER BOARD ELECTRICAL DUCTBANK AND MANHOLES, COMPLETE DOLLARS CENTS

N-23

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008
DATE: 06/02/09 08:45 PAGE: 24

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-202	14	EACH	DRAIN HOUSE CONNECTION FROM NEW DRAIN LINE TO BACK OF CURB (6" PVC) _____ DOLLARS _____ CENTS
S-203	200	LINEAR FOOT	DRAIN HOUSE CONNECTION BEYOND BACK OF CURB (6" PVC) _____ DOLLARS _____ CENTS
S-204	300	LINEAR FOOT	COLLECTOR LINE TO CATCH BASIN FOR DRAIN HOUSE CONNECTIONS (8" PVC) _____ DOLLARS _____ CENTS
S-205	4	EACH	ADJUST DRAIN CLEANOUT BOX _____ DOLLARS _____ CENTS
S-206	4	EACH	REMOVE MUD AND DEBRIS FROM METER BOX _____ DOLLARS _____ CENTS
S-207	4	EACH	REPLACE BROKEN WATER METER BOX _____ DOLLARS _____ CENTS

N-24

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008
DATE: 06/02/09 08:45 PAGE: 25

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-208	4	EACH	ADJUST WATER METER BOX DOLLARS CENTS
S-209	25	LINEAR FOOT	SEWER POINT REPAIR UP TO TEN FEET DOLLARS CENTS
S-210	30	LINEAR FOOT	SEWER POINT REPAIR BEYOND TEN FEET DOLLARS CENTS
S-211	5	EACH	REMOVE AND REPLACE EXISTING SEWER HOUSE CONNECTION FROM NEW MAIN TO BACK OF CURB DOLLARS CENTS
S-212	75	LINEAR FOOT	REMOVE AND REPLACE SEWER HOUSE CONNECTION BEYOND BACK OF CURB DOLLARS CENTS
S-213	6	EACH	REPLACE 5/8" AND 3/4" WATER HOUSE CONNECTION (FROM MAIN TO METER) DOLLARS CENTS

N-25

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 26

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-214	2	EACH	REPLACE 1" WATER HOUSE CONNECTION (FROM MAIN TO METER) DOLLARS CENTS
S-215	200	LINEAR FOOT	REPLACE 3/4" OR 1" WATER HOUSE CONNECTION (FROM METER TO PROPERTY LINE) DOLLARS CENTS
S-216	15	EACH	PLUG EXISTING DRAINS DOLLARS CENTS
S-217	200	CUBIC YARD	FILL DRAIN WITH MISSISSIPPI RIVER SAND DOLLARS CENTS
S-301	10	EACH	TREE REMOVAL (UP TO 10.0" DBH) DOLLARS CENTS
S-302	4	EACH	TREE REMOVAL (10.1" DBH TO 20.0" DBH) DOLLARS CENTS

N-26

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-36-0008
OTHER PROJECTS: 742-36-0008

DATE: 06/02/09 08:45 PAGE: 27

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-303	LUMP	LUMP SUM	TREE TRIMMING DOLLARS CENTS
S-304	4	EACH	ROOT PRUNING DOLLARS CENTS
S-305	100	LINEAR FOOT	ROOT TRENCHING DOLLARS CENTS
S-306	LUMP	LUMP SUM	RESTORATION OF EXISTING PLANT AND FLOWER BEDS DOLLARS CENTS

N-27