




KATHLEEN BABINEAUX BLANCO
GOVERNOR

**STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT**

P.O. Box 94245
Baton Rouge, Louisiana 70804-9245
www.dotd.louisiana.gov
225-379-1485



JOHNNY B. BRADBERRY
SECRETARY

June 13, 2007

**STATE PROJECT NO. 742-55-0004
FEDERAL AID PROJECT NO. 3035(002)
WESTSIDE BOULEVARD EXTENSION
TERREBONNE PARISH**

**SUBJECT: ADDENDUM NO. 2 (CONSTRUCTION PROPOSAL REVISION)
ELECTRONIC BIDDING AMENDMENT NO. 1**

Gentlemen:

Attached are the construction proposal revisions dated 06/13/07 on the captioned project for which bids will be received on Wednesday, June 27, 2007.

The following changes have been made:

1. Revised the special provision entitled "**Subletting of Contract**". (1 page)
2. Revised the special provision entitled "**Item S-002, Adjusting Waterlines**". (1 page)
3. Revised the Schedule of Items as follows: (3 pages)
 - a.) Deleted item 302-02-C-01, Class II Base Course (Avg. 5" thick) (Crushed Stone or Recycled PCCP); item 601-01-I, Portland Cement Concrete Pavement (8" thick), item 601-02-I, Portland Cement Concrete Pavement (8" thick) (Crossovers & Turnouts); and item 732-03-A-01, Plastic Pvmnt Striping (Broken Line) (4" width).
 - b.) Revised the quantity for item 302-02-C-02, Class II Base Course (10" thick) (Crushed Stone or Recycled PCCP).
 - c.) Added item 302-02-E-01, Class II Base Course (Avg 5" thick) (Crushed Stone or Recycled PCCP); item 601-01-G, Portland Cement Concrete Pavement (8" thick); item 601-02-G, Portland Cement Concrete Pavement (8" thick) (Crossovers & Turnouts); and item 732-03-A, Plastic Pavement Striping (Broken Line) (4" width).

Please note these revisions and substitute the construction proposal returnables (pages K-3, K-4, and K-8) in the proposal previously furnished you and bid accordingly. If bidding electronically, all amendments must be downloaded to this project prior to placing the on-line bid with Bid Express.

Very truly yours,

RANDAL D. SANDERS, P. E.
CONTRACTS & SPECIFICATIONS ENGINEER

Attachments

pc: Mr. Brian Buckel

Mr. Michael Stack

Mr. Alan Weber

Mrs. Dawn Sholmire

Ms. Margaret Thompson

Mr. John Oglesby

Mr. Masood Rasoulia

Terrebonne Parish Consolidated Government

FOR INFORMATION ONLY

SUBLETTING OF CONTRACT (1/83): In accordance with Subsection 108.01 of the Standard Specifications, the following items are designated as "Specialty Items":

- Item 728-01, Jacked or Bored Pipe (16" Dia., Steel, 3/8" Wall)
 - Item 729-01, Sign (Type A)
 - Item 729-21, U-Channel Post
 - Item 731-02, Reflectorized Raised Pavement Markers
 - Item 732-01-A, Plastic Pavement Striping (4" width)
 - Item 732-01-C, Plastic Pavement Striping (8" width)
 - Item 732-01-A, Plastic Pavement Striping (24" width)
 - Item 732-03-A, Plastic Pvmnt Striping (Broken Line) (4" width)
 - Item 732-04-A, Plastic Pavement Legends & Symbols (Arrow)
 - Item 732-04-C, Plastic Pavement Legends & Symbols (Only)
 - Item 741-11, Adjusting Water Valve and Meter Box
 - Item S-002, Adjusting Waterlines
 - Item S-003, Install 8" P.E. Sewer Force Main
-

FOR INFORMATION ONLY

ITEM S-002, ADJUSTING WATER LINES: This item consists of adjusting water lines in accordance with plan details and these specifications. All adjustments shall be coordinated with Terrebonne Parish Consolidated Waterworks District No. 1. Contractor shall provide a minimum 72 hour notice prior to beginning work:

Alignment and elevations of adjusted water lines shall be as directed. The Contractor shall conduct operations in such manner as to cause the least possible interruption to water service. All adjustments to existing A.C. waterlines must be performed by a Contractor properly certified by Louisiana Department of Environmental Quality.

The Contractor shall furnish any new pipe, fittings and other materials required in adjusting water lines. The Contractor shall replace pipe, fittings, and other materials in existing installations, which are damaged due to the contractor's operations. Pipe, fittings, and other material furnished by the Contractor shall be as specified on plans or at least equal in quality to those of the existing installation and of an acceptable type.

Adjusting water lines will be measured by the unit price per each adjustment.

Payment for adjusted water lines will be made at the contract unit price, which includes furnishing material as provided herein, and excavation and backfilling.

Payment will be made under:

<u>Item No.</u>	<u>Pay Item</u>	<u>Pay Unit</u>
S-002	Adjusting Water Lines	Per Each

FOR INFORMATION ONLY

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

DATE: 06/13/07 15:46 PAGE: 3

LEAD PROJECT: 742-55-0004
OTHER PROJECTS:

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
204-05-B	4	EACH	TEMPORARY SEDIMENT CHECK DAMS (STONE) DOLLARS CENTS
204-06	5,600	LINEAR FOOT	TEMPORARY SILT FENCING DOLLARS CENTS
302-02-C-02	20,114.2	SQUARE YARD	CLASS II BASE COURSE (10" THICK) (CRUSHED STONE OR RECYCLED PCCP) DOLLARS CENTS
302-02-E-01	4,598.4	SQUARE YARD	CLASS II BASE COURSE (AVG 5" THICK) (CRUSHED STONE OR RECYCLED PCCP) DOLLARS CENTS
304-01	397.52	TON	LIME DOLLARS CENTS
304-04-D	25,240	SQUARE YARD	LIME TREATMENT (TYPE D) (12" THICK) DOLLARS CENTS

FOR INFORMATION ONLY

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-55-0004
OTHER PROJECTS:

DATE: 06/13/07 15:46 PAGE: 4

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
401-02	20	CUBIC YARD	AGGREGATE SURFACE COURSE (ADJUSTED VEHICULAR MEASUREMENT) DOLLARS CENTS
501-01	961.7	TON	SUPERPAVE ASPHALTIC CONCRETE DOLLARS CENTS
601-01-G	13,736.4	SQUARE YARD	PORTLAND CEMENT CONCRETE PAVEMENT (8" THICK) DOLLARS CENTS
601-02-G	5,113.1	SQUARE YARD	PORTLAND CEMENT CONCRETE PAVEMENT (8" THICK) (CROSSOVERS & TURNOUTS) DOLLARS CENTS
601-04	25	EACH	PORTLAND CEMENT CONCRETE PAVEMENT CORING DOLLARS CENTS
701-04-E	274	LINEAR FOOT	STORM DRAIN PIPE ARCH (30" EQUIV. RCPA) DOLLARS CENTS

FOR INFORMATION ONLY

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

LEAD PROJECT: 742-55-0004
OTHER PROJECTS:

DATE: 06/13/07 15:46 PAGE: 8

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
729-21	25	EACH	U-CHANNEL POST DOLLARS CENTS
731-02	195	EACH	REFLECTORIZED RAISED PAVEMENT MARKERS DOLLARS CENTS
732-01-A	10,540	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (4" WIDTH) DOLLARS CENTS
732-01-C	295	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (8" WIDTH) DOLLARS CENTS
732-01-E	120	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (24" WIDTH) DOLLARS CENTS
732-03-A	1.064 MILE		PLASTIC PAVEMENT STRIPING (BROKEN LINE) (4" WIDTH) DOLLARS CENTS

FOR INFORMATION ONLY