




BOBBY JINDAL
GOVERNOR

STATE OF LOUISIANA
DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT

P.O. Box 94245
Baton Rouge, Louisiana 70804-9245

www.dotd.la.gov
225-379-1485



WILLIAM D. ANKNER, Ph.D.
SECRETARY

May 28, 2009

STATE PROJECT NO. 744-45-0007
FEDERAL AID PROJECT NO. ARR-4502(500)
ST. CHARLES WEST BANK MULTI-USE PATH
ST CHARLES PARISH

SUBJECT: ADDENDUM NO. 2 (CONSTRUCTION PROPOSAL REVISION)
ELECTRONIC BIDDING AMENDMENT NO. 1

Gentlemen:

The following proposal revisions dated 05/28/09 on the captioned project for which bids will be received on Wednesday, June 17, 2009 have been posted on <http://www.dotd.la.gov/cgi-bin/construction.asp>.

1. Added Special Provisions entitled, **S-005, Concrete Steps**, and **S-006, Concrete Overlook Slab**. (2 pages)
2. Revised the Schedule of Items as follows: (4 pages)
 - a. Deleted Item 706-03-C.
 - b. Added Items 706-03-A, 732-01-A-03, S-005, and S-006.

Please note these revisions in the proposal and bid accordingly. Mandatory electronic bidding is required for this project, and electronic bids and electronic bid bonds must be submitted via www.bidx.com for this letting date.

Sincerely,

RANDAL D. SANDERS, P. E.
CONTRACTS & SPECIFICATIONS ENGINEER

Attachments

cc: Mr. Brian Buckel
Mr. Michael Stack
Mr. Alan Weber
Mr. Stephen Meek
Mr. Eric Burges
Mr. Masood Rasoulian

S-005, CONCRETE STEPS:

DESCRIPTION OF WORK: This work consists of furnishing all materials, tools, labor, and incidentals necessary to install the concrete steps in accordance with these specifications and in conformity with the lines and dimensions shown on the plans.

MATERIALS: Materials shall conform to the following Sections, Subsections or other as specified:

Portland Cement Concrete	901
Reinforcing Steel	1009

CONSTRUCTION REQUIREMENTS:

1. Portland Cement Concrete shall be Class A concrete and have a minimum compressive strength at 28 days of 3800 psi.
2. Reinforcing Steel shall have minimum yield strength of 60,000 psi.

MEASUREMENT: Measurement shall be made by linear foot for work specified in this specification and as shown on the plans at locations requiring such.

PAYMENT: Payment for concrete steps will be made at the contract unit price per linear foot.

Payment will be made under:
Item S-005, Concrete Steps, per linear foot.

S-006, CONCRETE OVERLOOK SLAB:

DESCRIPTION OF WORK: This work consists of furnishing all materials, tools, labor, and incidentals necessary to install the concrete overlook slab in accordance with these specifications and in conformity with the lines and dimensions shown on the plans.

MATERIALS: Materials shall conform to the following Sections, Subsections or other as specified:

Portland Cement Concrete	901
Reinforcing Steel	1009

CONSTRUCTION REQUIREMENTS:

1. Portland Cement Concrete shall be Class A concrete and have a minimum compressive strength at 28 days of 3800 psi.
2. Reinforcing Steel shall have minimum yield strength of 60,000 psi.

MEASUREMENT: Measurement shall be made by linear foot for work specified in this specification and as shown on the plans at locations requiring such.

PAYMENT: Payment for concrete steps will be made at the contract unit price per linear foot.

Payment will be made under:

Item S-006, Concrete Overlook Slab, per linear foot.

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
 SCHEDULE OF ITEMS

DATE: 05/28/09 13:22 PAGE: 2

LEAD PROJECT: 744-45-0007
 OTHER PROJECTS:

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
705-03-A	120.0	SQUARE YARD	INCIDENTAL CONCRETE PAVING (4" THICK) _____ DOLLARS _____ CENTS
713-01	LUMP	LUMP SUM	TEMPORARY SIGNS & BARRICADES _____ DOLLARS _____ CENTS
716-01-A	1.5	TON	MULCH (VEGETATIVE) _____ DOLLARS _____ CENTS
717-01	31	POUND	SEEDING _____ DOLLARS _____ CENTS
718-01	1,030	POUND	FERTILIZER _____ DOLLARS _____ CENTS
727-01	LUMP	LUMP SUM	MOBILIZATION _____ DOLLARS _____ CENTS

744-45-0007

Addendum No. 2 /
 Amendment No. 1

(Rev. 05/28/09)

Page 3 of 6

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
 SCHEDULE OF ITEMS

DATE: 05/28/09 13:22 PAGE: 3

LEAD PROJECT: 744-45-0007
 OTHER PROJECTS:

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
729-01	132.0	SQUARE FOOT	SIGN (TYPE A) _____ DOLLARS _____ CENTS
729-21	47	EACH	U-CHANNEL POST _____ DOLLARS _____ CENTS
732-01-A-01	510	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (4" WIDTH) (WHITE) _____ DOLLARS _____ CENTS
732-01-A-02	180	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (4" WIDTH) (BLUE) _____ DOLLARS _____ CENTS
732-01-A-03	410	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (4" WIDTH) (YELLOW) _____ DOLLARS _____ CENTS
732-01-E	515	LINEAR FOOT	PLASTIC PAVEMENT STRIPING (24" WIDTH) _____ DOLLARS _____ CENTS

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
SCHEDULE OF ITEMS

DATE: 05/28/09 13:22 PAGE: 4

LEAD PROJECT: 744-45-0007
OTHER PROJECTS:

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
732-03-A	6.570	MILE	PLASTIC PAVEMENT STRIPING (BROKEN LINE) (4" WIDTH) _____ DOLLARS _____ CENTS
732-04-A	20	EACH	PLASTIC PAVEMENT LEGENDS & SYMBOLS (ARROW) _____ DOLLARS _____ CENTS
732-04-F	3	EACH	PLASTIC PAVEMENT LEGENDS & SYMBOLS (HANDICAP) _____ DOLLARS _____ CENTS
740-01	LUMP	LUMP SUM	CONSTRUCTION LAYOUT _____ DOLLARS _____ CENTS
-001	527	LINEAR FOOT	HANDRAIL _____ DOLLARS _____ CENTS
55-002	6	EACH	PRECAST CONCRETE BENCHES _____ DOLLARS _____ CENTS

744-45-0007

Addendum No. 2 /
Amendment No. 1

LOUISIANA DEPARTMENT OF TRANSPORTATION AND DEVELOPMENT
 SCHEDULE OF ITEMS

DATE: 05/28/09 13:22 PAGE: 5

HEAD PROJECT: 744-45-0007
 OTHER PROJECTS:

ITEM NUMBER	APPROXIMATE QUANTITY	UNIT OF MEASURE	PAY ITEM UNIT PRICE (IN WORDS, INK OR TYPED)
S-003	2	EACH	LOOP TYPE BICYCLE RACK _____ DOLLARS _____ CENTS
S-004	31	EACH	PRECAST PARKING STOPS _____ DOLLARS _____ CENTS
S-005	1.10	LINEAR FOOT	CONCRETE STEPS _____ DOLLARS _____ CENTS
S-006	1.50	LINEAR FOOT	CONCRETE OVERLOOK SLAB _____ DOLLARS _____ CENTS